

2-9

1 120375

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,614 - 0000

NE NW, SEC. 4, T 24 S, R 15 W/E

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Magnott Farms Well # 1

Operator: Pintraigon Petroleum

County Stafford 134.42

Name & Address 4101 N. East Douglas, Suite One

Well Total Depth 4136 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 9 Month: 2 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4133' PBD 4120' Perfs at 4013-19'

1st plug pump in 4 1/2" casing with 100 lbs. hulls and 20 sx cement,

2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 9 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 100 lbs. hulls and 20 sx cement,
pushed plug to 3900', shut in pressure 500 psi.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, and 125 sx cement.

Pumping pressure 0-400 psi and shut in 150 psi.

Plate and 2" collar welded on 8 5/8".

Remarks: Used 60# Pozmix 6% gel by B.J. Titan. Recovered 3044' of 4 1/2" casing.
(Wichita, Kansas description is necessary, use BACK of this form.)

INVOICED (with stamp) observe this plugging.

DATE 2-16-90

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 27474