

To: **120909** **3-29**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA 15-185-20770-0000  
NE NE SE, SEC. 11, T 24 S, R 15 W/E  
2310 feet from S section line  
66 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911  
Operator: RAMA Operating Co., Inc.  
Name & Address P.O. Box 159  
Stafford, KS 67578

Lease Name Hardten Well # 1  
County Stafford  
Well Total Depth 4230 137.47 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 29 Month: 3 Year: 1994

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943  
w/ 4 1/2" at 4229' w/275 sx cement, Perfs at 4126-4230'

1st plug sand 4 1/2" casing back to 4075' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 p.m. Day: 29 Month: 3 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4075' and dumped 4 sx cement on top  
of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
4-1-94  
**APR 01 1994**  
CONSERVATION DIVISION  
Wichita, Kansas

~~Plugging Technician~~ observe this plugging.

Signed Steve Middleton  
(TECHNICIAN)

**INVOICED**  
DATE APR 08 1994  
INV. NO. 40392