

1 080595

FEB 4 1987

API NUMBER 15- 185-20,422-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2 W/2 NW/4, SEC. 11, T 24 S, R 15 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3960 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5025

Lease Name Harkness Well # 5

Operator: Tomlinson Oil Co. Inc.
Name & Address: Box 1588
Great Bend, KS 67530

County Stafford 131.82

Well Total Depth 4056 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Tomlinson Oil Co. Inc. License Number 5025

Address Box 1588, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 4 Month: 2 Year: 1987

Plugging proposal received from Stan Freeman

(company name) Tomlinson Oil Company (phone) 316-792-2361

were: 5 1/2" at 4054' PBDT 2574' Perfs at 2517-21, 2538-46' Cast Iron Bridge Plug at 2574'
1st plug pump 2 sx hulls and 35 sx cement, 2nd plug pump 15 sx gel-fill to 750',
3rd plug pump 32' sx cement, 4th plug pump 2 sx gel and 40 sx cement,
5th plug pump 45 sx cement down 8 5/8" annulus.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:25 p.m. Day: 4 Month: 2 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 35 sx common cement,
2nd plug pumped 16 sx gel and 40 sx cement (60/40 Pozmix)

Maximum pressure 1750 psi and shut in 1250psi.
(60/40 Pozmix)

3rd plug pumped 61 sx cement down 8 5/8" annulus. Maximum pressure 200 psi and shut in 100 psi.

Maximum pressure 200 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix by B.J. Titan. Also used common cement by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to XXXXXXX) observe this plugging.

DATE 2-16-87

INV. NO. 16127

Signed J.A. Mead (TECHNICIAN) CONSERVATION DIVISION Wichita, Kansas

2-12-87
FEB 12 1987
DAN