

2 050257

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,526 ⁰⁰⁰⁰ R

SWNE, SEC. 10, T 27 S, R 7 W/E

4290 feet from N/S section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

Lease Name McClure Well # 1-10

Operator: Allen Drilling Company

County Kingman 135.20

Name & Address Box 1389

Well Total Depth 4160 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Company tools License Number

Address

Company to plug at: Hour: 7:00p.m. Day: 22 Month: 5 Year: 19 85

Plugging proposal received from

(company name) (phone)

were: 35 sacks at 900 feet; 35 sacks at 600 ft.; 25 sacks at 60 feet; 10 sacks in rat hole

Plugging Proposal Received by Glenn Ward (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:45p.m. Day: 23 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT Ran drill pipe to 900 feet. Circulated hole for 10 minutes.

Spotted 35 sacks of cement at 900 feet. Displaced with mud. Pulled drill pipe to 600 feet and spotted 35 sacks of cement. Pulled drill pipe to 60 feet and circulated cement to surface. Circulated 10 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
05-31-85
MAY 31 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Howco Ticket #083618-7
(If additional description is necessary, use BACK of this form.)

INVOICED

(See also Job) observe this plugging.

DATE 6-6-85

Signed Glenn Ward (TECHNICIAN)
WC RO

INV. NO. 8332
5-23