

7-10

2-010077³⁷
[Signature]

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-079-20,115⁰⁰⁻⁶⁰' D #15260
SW,NW,SE, SECTION 14 TOWNSHIP 23 RANGE 2W

OPERATOR LICENSE # 100 1650' FEET FROM S SECTION LINE
2310' FEET FROM E SECTION LINE

OPERATOR STATE OF KANSAS
NAME & WICHITA STATE OFFICE BLDG.
ADDRESS ROOM #2078, 130 S. MARKET

LEASE NAME: RUTH-HAURY (EWY) 1-SWD
COUNTY: HV

WELL TOTAL DEPTH: 3554'

PIPE: _____

SURFACE CASING: 10 3/4" @ 215'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD X D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: GRESSEL OILFIELD SERVICE INC.
ADDRESS: BOX 607, BURRTON, KS 67020-0607 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 10 MONTH: 7 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: MICHAEL R. WILSON
COMPANY NAME: STATE OF KANSAS PHONE: 316-337-6231
WERE: SAND TO 3440' AND TOP WITH 10 SKS. CMT. PROFORATE 7"
CASING @ 400' AND CIRCULATE CMT. TO THE SURFACE. 7"
CASING @ 3554' PROFORATIONS FROM 349 FT. TO 3530'.

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 20:00 DAY: 10 MONTH: 7 YEAR: 1995

ACTUAL PLUGGING REPORT:
PULLED 2978.17' OF 2 3/8" TUBING. RAN WIRELINE TO
3550'. RAN 3380.82' OF TUBING. PUMPED 40 SKS. CMT. WITH
3% CA. CL. AT 3380.82' PULLED TUBING. PERFORATED WITH 4
HOLES AT 403 TO 404'. RAN 2 3/8 TUBING TO 407.86' AND
CIRCULATED 132 SKS. CMT. TO SURFACE.

REMARKS: USED 60/40 POXMIX W/4% GEL 3% CA. CL. BY UNITED INVOICE
#2003
I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
Michael R. Wilson RECEIVED
KANSAS CORPORATION COMMISSION

JUL 27 1995
7-27-95
CONSERVATION DIVISION
WICHITA, KS
FORM CP-2/3
REV. 3/90

DW