

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-15

2-010068

15-155-0664-0000
3-19-98

API NUMBER: _____

NE SE NE, SECTION 2 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5526 1660 FEET FROM ^N SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR HAROLD J MILBURN
NAME & 7315 N MONROE
ADDRESS HUTCHINSON KS 67502

LEASE NAME: WHITE 1 109.69
COUNTY: RENO
WELL TOTAL DEPTH: 3375'

PIPE: _____

SURFACE CASING: 8-5/8" @ 647'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC
ADDRESS: BOX 209, CHASE KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 15 MONTH: 2 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: HAROLD J MILBURN

COMPANY NAME: HAROLD J MILBURN PHONE: 316-663-1616

WERE: SAND TO 3260' & TOP W/5 SX CMT - SHOOT PIPE OFF -
PULL PIPE TO 700' & SPOT 50 SX CMT - PULL PIPE TO 350'
& CIRC CMT TO SURF
5-1/2" CSG @ 3375' - PERFS @ 3312' TO 3332'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 15:30 DAY: 15 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:
SANDED TO 3260' & TOPPED W/5 SX CMT - SHOT PIPE OFF @
1917' - PULLED PIPE TO 747' & SPOTTED 50 SX CMT W/200
LBS HULLS - PULLED PIPE TO 401' & CIRC 95 SX CMT TO
SURF RETRIEVED 1917' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ W/4% GEL BY ALLIED #1877

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
Michael R. Wilson (AGENT)

RECEIVED
CORPORATION COMMISSION
3-10-95
MAR 10 1995
FORM CP-2/31
REV 12/93
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE MAR 14 1995
INV. NO. 42369