

2 080106

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-079-20,592-0000

SW NW NW, SEC. 28, T 23 S, R 3 W/EX

4290 feet from W/S section line

4950 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5330

Lease Name Holzrichter Well # 1

Operator: Excalibur Production Co., Inc.

County Harvey 109.01

Name & Address Box 278

Well Total Depth 3354 feet

McPherson, Kan. 67460

Conductor Pipe: Size 10 3/4 feet 312

Surface Casing: Size feet

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: Day: 6 Month: December Year: 1985

Plugging proposal received from Milard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Plug back TD @ 3343

Perfs @ 3291 to 3322

Shot 5 1/2 @ 2400 and pulled 2400 feet of 5 1/2 casing.

Sand & gravel to 3240 with 6 sxs.

Plugging Proposal Received by Dist. #2 (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 1245 Day: 29 Month: January Year: 1986

ACTUAL PLUGGING REPORT Sand and gravel to 3240 plus 6 sxs common. Swedge on to 10 3/4 and pump 5 sxs gel, 3 sxs hulls and 200 sxs 60-40 Poz. 2%; Maximum pump pressure 500 psig; shut in pressure 200 psig. Will check back to see if cement fell any and if so will recontact the operator for additional cement required.

Remarks: United ticket #0569

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging

RECEIVED

DATE FEB 6 1986

FEB 5 1986

Signed Reed E. O'Connor (TECHNICIAN)

INV. NO. 12382

CONSERVATION DIVISION Wichita Kansas