

2 100134

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 079-20,377-0000

NW NW SW, SEC. 10, T 23 S, R 3 W ~~XX~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 5526

Operator: Harold Milburn
Name & Address 7315 N. Monroe
Hutchinson, KS 67502

_____ feet from S section line

_____ feet from E section line

Lease Name Goodyear Well # 1

County Harvey 110.11

Well Total Depth 3388 feet

~~CONCRETE~~ Pipe: Size 4 1/2 feet 3388

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well _____ Gas Well x Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated perf 326-3266 3270-3274

Plugging Contractor Gressel Oilfield Service License Number 5823

Address Box 286, Burrton, KS

Company to plug at: Hour: 4:00 Day: 11 Month: 12 Year: 19 85

Plugging proposal received from Ed Gressel

(company name) Gressel Oilfield Service (phone) _____

were: sand 3200 feet and dump 4 sacks of cement

pump 3 sacks of hull, 12 sacks of gel, 125 sacks of cement

Plugging Proposal Received by SVG
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 4:00 Day: 13 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT Plug bottom from 3295 feet to 3200 feet with sand and dump 4 sacks of cement with bailer. Shot pipe at 2000'. Shot again at 1470 feet and pulled casing. Set wood and rock bridge at 400 feet. Filled to surface with 7 yards of redi-mix cement.

Remarks: Haven Redi-Mix #6053

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 1 1986
INV. NO. 13235

STATE CORPORATION COMMISSION
Signed J. L. Sander
(TECHNICIAN)
MAR 31 1986
3-31-86
CONSERVATION DIVISION
Wichita, Kansas