

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

12-30

API NUMBER: 15-079-20495-0000

5/2-SW-SE SECTION 10 TOWNSHIP 23 RANGE 3W

OPERATOR LICENSE # 5526  
OPERATOR Harold J. Milburn  
NAME & 7315 N. Monroe  
ADDRESS Hutchinson, KS 67502

330 FEET FROM S SECTION LINE  
1980 FEET FROM E SECTION LINE  
LEASE NAME: Adrian # 1  
COUNTY: Harvey  
WELL TOTAL DEPTH: 3305' 102.41  
PIPE: \_\_\_\_\_  
SURFACE CASING: 8 5/8" @ 327'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Mike's Testing & Salvage Inc.  
ADDRESS: P.O. Box 467 Chase, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 14:00 DAY: 30 MONTH: 12 YR: 1998

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Mike's Testing & Salvage Inc. PHONE: 316-938-2943  
WERE: Sand to 3210' and top with four sacks of cement. Shoot pipe off. Pull pipe to 375' and circulate cement to the surface. 4 1/2" casing at 3302' Perforations at 3260 to 3279.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (\_\_\_\_\_) PART (  ) NONE (\_\_\_\_\_)

COMPLETED: HOUR: 16:00 DAY: 30 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT: Sanded to 3190' and topped with four sacks cement. Shot pipe off at 1820'. Pulled pipe to 373' and circulated one hundred and fifteen sacks cement to the surface. Retrieved 1820' of 4 1/2" casing. (55 jts)

REMARKS: Used 60/40 pos mix with 4% gel by Allied-Invoice # 9014

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson  
Mike Wilson

*Rec'd 1-11-99  
KCC  
TJW*

1-15-99  
60555