

2 050366

To: .
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,768 0000

N/2 SE, SEC. 30, T 28 S, R 1 (W)X

1980 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4760

Lease Name Towers Well # 1

Operator: Flatland Operations

County Sedgwick 127.43

Name & Address 927 N. K-15 Highway

Well Total Depth 3921 feet

Derby, KS 67037

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger License Number 5302

Address Wichita, KS

Company to plug at: Hour: 1 p.m. Day: 1 Month: 4 Year: 1986

Plugging proposal received from

(company name) (phone)

were: 35 sacks at 1100'

35 sacks at 270'

25 sacks at 60'

10 sacks in rat hole

5 sacks in water well

Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5 p.m. Day: 1 Month: 4 Year: 1986

ACTUAL PLUGGING REPORT Ran drill pipe to 1150 feet, circulated hoe with mud; then spotted 35 sacks of cement. Pulled drill pipe to 270 feet and spotted 35 sacks of cement.

Pulled all drill pipe and pushed plug to 60 feet. Ran drill pipe back down to pug and circulated cement to surface. Circulated 10 sacks of cement in rat hole and 5 sacks in water well.

Remarks: United 9290

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE APR 11 1986

Signed *Glen F. Ward*
(TECHNICIAN)

INV. NO. 13378 MAY 08 1986 AUG 7 1986