

2 030278

15-155-62777-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp 1939
NE, SEC. 11, T. 23 S, R. 4 W
3960' feet from N/S section line
1720' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 5271
Operator: S+K. Oil Company
Name & Address Box 559
Julesa, Ok. 74101

Lease Name Sabin "B" Well # 3
County Reno 109.66
Well Total Depth 3374' feet
Conductor Pipe: Size 15 1/2" feet 11.3' cement
Surface Casing: Size 12 1/2" feet 571' cement

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gressell Oil Field Service License Number 5823
Address Box 286, Burrton, Ks. 67020

Company to plug at: Hour: 09:00 AM Day: 7 Month: 8 Year: 19 85

Plugging proposal received from Eddie Gressell
(company name) Gressell Oil Field Service (phone) 316-463-5161

were: 8 5/8" csg. at 3250' / 125 ex. cement. 8 5/8" csg. parted at 380'
run tub as far as possible spot .50 ex. cement. pull
tub 370' spot cement to surface.

Plugging Proposal Received by Dist # 2 W.K.
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 13:45 Day: 7 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT Ran 2 3/8" tub to 2750', Halliburton
Services # 099031-9, spotted 4 ex. hells, 10 ex. gel,
50 ex. com. cement. pulled tub to 370', pumped 4 ex. hells,
10 ex. gel, 300 ex. cement. C.H., pulled tub let set 1 1/2 hrs.
ran tub 60', pumped. 7.5 ex. com. cement, cement. circ.
between 8 5/8" csg. and 12 1/2" csg. left 8 5/8" csg. full of cement.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
AUG 23 1985

DATE 9705
INV. NO. _____

WK

Signed Don Thompson
(TECHNICIAN)
RO

AUG 23 1985
8-23-85
CONSERVATION DIVISION