

11-16

RECEIVED  
KANSAS CORPORATION COMMISSION 2-010059

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

DEC 07 1994

CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-079-20,208-0000  
SW NW NE, SECTION 18 TOWNSHIP 23 RANGE 3W

OPERATOR LICENSE # 6568 4290 FEET FROM S SECTION LINE  
2310 FEET FROM E SECTION LINE

OPERATOR KAISER-FRANCIS OIL CO  
NAME & P O BOX 21468  
ADDRESS TULSA OK 74121-1468

LEASE NAME: WILEY #6 107  
COUNTY: HARVEY 109.20  
WELL TOTAL DEPTH: 3360' (3300')

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 332'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: KELSO CASING PULLING  
ADDRESS: BOX 347, CHASE KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 0830 DAY: 16 MONTH: 11 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JOHN GLENN  
COMPANY NAME: KAISER-FRANCIS OIL CO PHONE: 316-564-3214

WERE: SET CIBP @ 3300' & TOP W/2 SX CMT - SHOOT OFF PIPE -  
PULL TO 540' & SPOT 35 SX CMT - PULL TO 380' & CIRC CMT  
TO SURF - OPEN HOLE @ 3360' TO 3369' - 5-1/2" CSG @  
3360' - PERFS @ 3344' TO 3350'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1230 DAY: 16 MONTH: 11 YEAR: 1994

ACTUAL PLUGGING REPORT:  
SET CIBP @ 3300' & TOPPED W/2 SX CMT - SHOT PIPE OFF  
@ 2550' - PULLED PIPE TO 550' & SPOTTED 35 SX CMT -  
PULLED PIPE TO 355' & CIRC 115 SX CMT TO SURF - CMT  
FELL 125' & WAS TOPPED OFF W/45 SX CMT ON 11/17/94 -  
RETRIEVED 2550' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ 4% GEL BY ALLIED #6835 & #6836

I DID OBSERVE THIS PLUGGING.

INVOICED

Michael R. Wilson  
Michael R. Wilson (AGENT)

DATE 12-8-94

FORM CP-2/3  
REV. 3/90

INV. NO. 41867

DW