

11-21

2-100651

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-079-20,196-0000

E/2 NW NE, SECTION 18 TOWNSHIP 23 RANGE 3W

OPERATOR LICENSE # 6568 3960 FEET FROM S SECTION LINE
1650 FEET FROM E SECTION LINE

OPERATOR Kaiser-Francis Oil Company
NAME & P. O. Box 21468
ADDRESS Tulsa, OK 74121-1468

LEASE NAME: Wiley #5
COUNTY: Harvey
WELL TOTAL DEPTH: 3363' 109.29

CONDUCTOR PIPE: 5-1/2" @ 3355'/100 sx

SURFACE CASING: 8-5/8" @ 335'/125 sx

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: OH 3355-63'

PLUGGING CONTRACTOR: Gressel Oil Field Service
ADDRESS: Box 607, Burrton, KS 67020 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 11:30a DAY: 21 MONTH: 11 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: John Hatcher
COMPANY NAME: Kaiser-Francis PHONE: 918-494-0000

WERE: Run tubing to 3300' - pump 35 sx cmt - pull pipe to 500' - circ to surface inside 5-1/2" - hook up to 8-5/8" & pump 75 sx cmt - shut in.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 2:00p DAY: 21 MONTH: 11 YEAR: 1990

ACTUAL PLUGGING REPORT:
Ran tubing to 3300' - pumped 35 sx displaced - tagged top at 3201' - ran tub to 500' - circ 54. sx 60/40 2% gel to surface - hooked on to 8-5/8" & pumped 71 sc cmt - shut in well at 250#.

Rec'd 1-2-91

REMARKS: B. J. Titan #635612 HOWCO #037070

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 1-4-91

INV. NO. 30306
11-21

John Sanders
John Sanders (AGENT)

aw