

11-17

RECEIVED
KANSAS CORPORATION COMMISSION

2-010060

DEC 07 1994

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 207B
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: SPUD 11/7/48 15-079-00534-0000
N. NE NE, SECTION 18 TOWNSHIP 23 RANGE 3W

OPERATOR LICENSE # 6568 4950 FEET FROM S SECTION LINE
990 FEET FROM E SECTION LINE

OPERATOR KAISER-FRANCIS OIL CO
NAME & P O BOX 21468
ADDRESS TULSA OK 74121-1468

LEASE NAME: WILEY #4 109.20
COUNTY: HARVEY
WELL TOTAL DEPTH: 3360'

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 275'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING
ADDRESS: BOX 347, CHASE KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 1400 DAY: 17 MONTH: 11 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JOHN GLENN
COMPANY NAME: KAISER-FRANCIS OIL CO PHONE: 316-564-3214

HERE: SET CIBP @ 3270' & TOP W/2 SX CMT - SHOOT OFF PIPE -
PULL TO 540' & SPOT 35 SX CMT - PULL TO 325' & CIRC CMT
TO SURF - OPEN HOLE @ 3312' TO 3360' - 5-1/2" CSG @
3312'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 1815 DAY: 17 MONTH: 11 YEAR: 1994

ACTUAL PLUGGING REPORT:
SET CIBP @ 3270' & TOPPED W/2 SX CMT - SHOT PIPE OFF
@ 1995' - PULLED PIPE TO 500' & SPOTTED 35 SX CMT -
PULLED PIPE TO 280' & CIRC 100 SX CMT TO SURF -
RETRIEVED 1995' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ 4% GEL BY ALLIED #6836

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 12-8-94

INV. NO. 41862

Michael R. Wilson
Michael R. Wilson (AGENT)

FORM CP-2/3
REV. 3/90