

RECEIVED
KANSAS CORPORATION COMMISSION: 2-18

2-100760 152
R

FEB 28 1992

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 11/5/48 15-079-00532-0000

NE SW NE, SECTION 18 TOWNSHIP 23 RANGE 3W

OPERATOR LICENSE # 5120 3630 FEET FROM S SECTION LINE
1320 FEET FROM E SECTION LINE

OPERATOR Kaiser Francis Oil Co.
NAME & Box 21468
ADDRESS Tulsa, OK 74121-1468

LEASE NAME: Wiley #3

COUNTY: Harvey

WELL TOTAL DEPTH: 3358'

PIPE: 5-1/2" @ 3308'/250 sx

SURFACE CASING: 8-5/8" @ 272'

109.13

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: Open hole 3308' - 3358'

PLUGGING CONTRACTOR: Gressel Oilfield Serv.
ADDRESS: Burrton, KS LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 12 MONTH: 2 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Dean Frank/John Glenn
COMPANY NAME: Kaiser Francis Oil Company PHONE:

WERE: Pump 35 sx cmt on bottom thru tub - pull tub - shoot
pipe @ 350' - circ to surf inside & outside 5-1/2"

PLUGGING PROPOSAL RECEIVED BY: John Sanders
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()

COMPLETED: HOUR: 11:00a DAY: 18 MONTH: 2 YEAR: 1992

ACTUAL PLUGGING REPORT:
1ST DAY - Pumped 60/40 3% cc 4% gel, 35 sx on bottom
thru tub - pulled tub - shot pipe @ 340' - pumped water
well - did not circ - pumped 100 sx cmt & displaced to
350' - tagged well @ 288' - weld valve 8-5/8" - shot
well @ 257' - hooked up to backside - pumped 50 sx cmt
& cmt backed up in cellar - hooked up to 5-1/2" &
pumped 150 sx cmt - shut in well @ 100# 15' outside 5 -
1/2". 2/18/92 - cmt fell 70' inside 5-1/2" - slurry
mix 1 yd to fill hole.

REMARKS: B.J. Titan #057416, #057417 & Haven Redimix #11330

INVOICED DID OBSERVE THIS PLUGGING.

DATE MAR 10 1992

INV. NO. 34714

J. L. Sanders
J. L. Sanders (AGENT)

FORM CP-2/3
REV. 3/90

plw