

RECEIVED
KANSAS CORPORATION COMMISSION

2-13
2-100761
153
R

FEB 28 1992

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 7/13/48 15-079-00533-0000

SE NE NE, SECTION 18 TOWNSHIP 23 RANGE 3W

OPERATOR LICENSE # 5120 4290 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR Kaiser Francis Oil Co.
NAME & Box 21468
ADDRESS Tulsa, OK 74121-1468

LEASE NAME: Wiley #1

COUNTY: Harvey

WELL TOTAL DEPTH: 3347'
PIPE: 5-1/2" @ 3312'/100 sx
SURFACE CASING: 8-5/8" @ 333'

108.77

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: Open hole 3312' - 3347'

PLUGGING CONTRACTOR: Gressel Oilfield Serv.
ADDRESS: Burrtton, KS LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 11 MONTH: 2 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Dean Frank/John Glenn
COMPANY NAME: Kaiser Francis Oil Company PHONE: _____

WERE: Pump 35 sx 3% cc cmt thru tub - shoot well @ 400' -
circ inside & outside 5-1/2"

PLUGGING PROPOSAL RECEIVED BY: John Sanders
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 3:00p DAY: 13 MONTH: 2 YEAR: 1992

ACTUAL PLUGGING REPORT:
1ST DAY - Pumped 60/40 3% cc 4% gel, 35 sx on bottom
thru tub - pulled tub - shot 5-1/2" @ 388' & circ 190
sx cmt - cmt fell to 350' - misfired 1 shot @ 340' -
lost line & pipe in well - shot well @ 240' - welded
valve on 8-5/8" & pumped (circ) 65 sx cmt - shut in
8-5/8" and pumped 35 sx cmt down 5-1/2" - shut well in
at 100#. 2/14/92 - Well fell 15' to surface.

REMARKS: B.J. Titan #057415, #057417

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE MAR 10 1992

INV. NO. 34713

J. L. Sanders
J. L. Sanders (AGENT)

FORM CP-2/3
REV. 3/90

Dew