

02- 10214

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-19013-00-<sup>02</sup>~~00~~ Spot:  
Sec: 18 Twnshp & Dir: 23 S Rng & Dir: 3 W  
Feet: 692 frm N/S: S Feet: 2015 frm E/W: E  
Lease/Unit Name: LECLERC Well Number: 0-1  
County: HARVEY Total Vertical Depth: 3372 feet

Operator License No.: 101  
Operator Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 10.75 feet: 270  
Production: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/02/1999 5:30 PM  
Plug Co. License No.: 3004 Plug Co. Name: Gressel Oilfield Service, Inc.  
Proposal Received from: Michael R. Wilson Company Name: Kansas Corporation Commission-District  
OpRepPhoneNo: (316) 337-6231

Were: Sand to 3,285' and top with 5sxs cement. Shoot 5 1/2" casing and pull pipe. Run 2 3/8" tubing to 560' and spot 35sxs cement. Pull 2 3/8" tubing to 325' and circulate cement to the surface. 5 1/2" casing @ 3,324'. Open hole from 3,324' to 3,372'.

Plugging Proposal Received By: Michael R. Wilson WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 09/03/1999 5:30 PM

Actual Plugging Report:

Sanded to 3,285' and topped with 5sxs cement. Perforated 5 1/2" casing at 560'-561 and 325'-326'. Ran 2 3/8" tubing to 560' and spotted 35sxs cement. Pulled tubing to 325' and circulated 240' cement to the surface.

RECEIVED  
KCC DISTRICT #2

JUN 21 2000

WICHITA, KS

Remarks: Used 5sxs common by Gressel Oil Field Service on bottom. Used 60/40 posmix w/ 4%gel by United. Invoice # 4703  
Anhydrite Plug: No BottomPlug: DakotaPlug: No  
Plugged through:

I (did ~~not~~) observe this plugging.

Signed Michael R. Wilson  
(TECHNICIAN)