

2-060226

E-10,087.7

7-2

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER:

15-079-3007 3-0000

01

VR-KCC

SE, SECTION 18 TOWNSHIP 23S RANGE 3W

OPERATOR LICENSE # 100

1650 1710

FEET FROM S SECTION LINE

OPERATOR KCC

455 513

FEET FROM E SECTION LINE

NAME & 130 So. Market

ADDRESS Wichita, Ks. 67202

LEASE NAME: Martindale # 05

COUNTY: Harvey

WELL TOTAL DEPTH: 3368'

PIPE: 5 1/2" @ 3330'

SURFACE CASING: 10 3/4" @ 245'

ABANDONED OIL WELL: GAS WELL: INPUT WELL XX SWD: D&A:

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Gressel Oilfield Service

ADDRESS: Box 607, Burrton, Ks. 67020 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YEAR: _____

PLUGGING PROPOSAL RECEIVED FROM: Doug Louis

COMPANY NAME: KCC PHONE: _____

WERE: See below

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (XX)

COMPLETED: HOUR: _____ DAY: 2nd MONTH: September YEAR: 1997

ACTUAL PLUGGING REPORT: Sanded back 3280' dump bailed 5 sacks cement perf casing 560' FS and 325' FS. Ran tubing to 560' FS, spotted 35 sacks cement. Pulled tubing to 325' FS. Circulate cement to surface, let set overnight. Ran 1" PVC to 60' FS inside and outside of casing. Filled casing to surface.

REMARKS: _____

I DID NOT OBSERVE THIS PLUGGING.

Dave Wertz
Dave Wertz

FORM CP-2/3
REV. 3/90

Rec'd
7/25/97

R

~~INVOICED~~

DATE _____

INV. NO. _____