

02- 10213

N2S2SE JR KCC

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-19012-00-00 Spot: N2N2SE
Sec: 18 Twnshp & Dir: 23 S Rng & Dir: 3 W
Feet: 1047 frm N/S: S Feet: 1290 frm E/W: E
Lease/Unit Name: LECLERC Well Number: 1
County: HARVEY Total Vertical Depth: 3368 feet

Operator License No.: 101
Operator Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 12.25 feet: 268
Production: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/29/1999 8:00 PM
Plug Co. License No.: 3004 Plug Co. Name: Gressel Oilfield Service, Inc.
Proposal Received from: Michael R. Wilson Company Name: Kansas Corporation Commission-District
OpRepPhoneNo: (316) 337-6231

Were: Sand to 3,210 and top with 5sxs cement. Shoot 5 1/2" casing and pull pipe. Run 2 3/8" tubing to 560' and spot 35sxs cement. Pull 2 3/8" tubing to 325' and circulate cement to the surface. 5 1/2" casing@3,263. Open hole from 3,263' to 3,368'.

Plugging Proposal Received By: Michael R. Wilson WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 09/02/1999 5:30 PM

Actual Plugging Report:

Sanded to 3,210' and topped w/10sxs cement. Perforated 5 1/2" casing @ 560'-561' and 325'-326'. Ran 2 3/8" tubing to 560' and spotted 50sxs cement. Pulled tubing to 325' and attempted to circulate hole- no circulation. Ran tubing to 560' and respotted 50sxs cement. Waited on cement to set up. Pulled tubing 325' and circulated 360sxs cement to the surface.

RECEIVED
KCC DISTRICT #2
JUN 21 2000
WICHITA, KS

Remarks: Used 10sxs common by Gressel Oil Field Service on bottom. Used 60/40 posmix w/4%gel by United. Invoice # 4701
Anhydrite Plug: No BottomPlug: DakotaPlug: No
Plugged through:

I (did / did not) observe this plugging.

Signed Michael R. Wilson
(TECHNICIAN)