

6-20

2-010155

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

15-079-19041-0000

API NUMBER: FEE FUND PLUG

S/2 SE SE, SECTION 18 TOWNSHIP 23 RANGE 3W

OPERATOR LICENSE # 100 347 FEET FROM S SECTION LINE  
OPERATOR KANSAS CORPORATION COMMISSION 6437 FEET FROM E SECTION LINE  
NAME & 130 SOUTH MARKET #2125  
ADDRESS WICHITA, KS 37202

LEASE NAME: Le CLERC #2  
COUNTY: HARVEY  
WELL TOTAL DEPTH: 3350'  
PIPE:  
SURFACE CASING: 13 1/4" @ 297'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: CONTROL #970176-11

PLUGGING CONTRACTOR: GRESSEL OILFIELD SERVICE INC

ADDRESS: P.O. BOX 607, BURRTON, KS 67020 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 20 MONTH: 6 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MICHAEL R. WILSON

COMPANY NAME: KCC, DISTRICT II PHONE: (316) 337-6231

WERE: SAND TO 3200' AND TOP WITH 10 SACKS OF CEMENT. PERFORATE 7" CASING AT 560' AND 350'.  
RUN TUBING TO 560' AND SPOT 50 SACKS OF CEMENT. PULL TUBING TO 350' AND CIRCULATE CEMENT TO  
THE SURFACE. 7" CASING AT 3312'

OPEN HOLE FROM 3254' TO 3350'  
RECEIVED  
KANSAS CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON JUL 08 1997

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( ) NONE (  )

COMPLETED: HOUR: 12:00 DAY: 20 MONTH: 6 YEAR: 1997 CONSERVATION DIVISION WICHITA, KS

ACTUAL PLUGGING REPORT: SANDED TO 3200' AND TOPPED WITH 10 SACKS OF CEMENT. PERFORATED 7"  
CASING AT 560' AND 350'. RAN 2 3/8" TUBING TO 560' AND SPOTTED 50 SACKS OF CEMENT WITH  
2% Ca Cl<sub>2</sub>. PULLED 2 3/8" TUBING TO 350' AND CIRCULATED 310 SACKS OF CEMENT WITH 2% Ca Cl<sub>2</sub>  
TO THE SURFACE.

REMARKS: 60/40 POZ 4% GEL 360 SACKS CEMENT & 6 SACKS Ca Cl<sub>2</sub> UNITED #4864

I DID NOT OBSERVE THIS PLUGGING.

*Michael R Wilson*  
MICHAEL R. WILSON