


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

RECEIVED
APR 27 1971
S & K OIL CO.
K & P OIL CO. Form CH-4
LOUIS KAHAN, ET, AL
15-079-19055-0000

WELL PLUGGING RECORD

Harvey County, Sec. 18 Twp. 23S Rge. 3W (E) (W)
Location as "NE/CNW&SW" or footage from lines. ~~XSWXHXSEXX~~ C NE SW
Lease Owner K & P Oil Co.
Lease Name Sabin "C" Well No. 4
Office Address P. O. Box #559, Tulsa, Oklahoma 74101
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 1-2- 1964
Application for plugging filed 4-1 1971
Application for plugging approved Mar. 4, 8 1971
Plugging commenced Mar. 30 1971
Plugging completed April 5 1971
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Mississippi Depth to top 3292 Bottom _____ Total Depth of Well 3380 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi		3259	3292	10 3/4	266	None
Cherokee		3152	3259	5 1/2	3291	2400.70
Lansing		2541	2985			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back 25' in pipe and dumped 5 sacks of cement. Shot pipe off at 2400'70". Pulled pipe and mudded hole to 250'. Finished filling hole with ready ready-mix-cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1971
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Bert Self (If additional description is necessary, use BACK of this sheet)
Address Hutchinson, Kansas



Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans. 67501 (Address)

SUBSCRIBED AND SWORN to before me this 6th day of April, 19 71

My commission expires October 18, 1973 Notary Public.

K & P OIL CO.
P.O. BOX 682, TULSA, OKLAHOMA
Zip 74101

15-079-19055-0000

SUPPLEMENTAL COMPLETION REPORT

Company: K & P Oil Co.
Farm & Well: Sabin "C" No. 4 C NE SW Sec. 18-23-3
Harvey County, Kansas

Commenced: 12-24-63 Elev.: 1465' KB
Completed: 1-24-64 Rotary TD 3292'
Initial Production: 9 Bbls Oil Cable Tool TD 3380'
30 Bbls water /day

Casing Record:
10 3/4" @ 266' w/275 sax
5 1/2" @ 3291' w/ 150 sax

FORMATION TOPS:

Lansing	2541
Base of Kansas City	2985
Cherokee	3152
Mississippi	3259

LOG:

0	200	Sand
210	475	Shale
475	2690	Lime & shale
2690	3259	Lime
3259	3268	Tan to cream course crystalline dense slightly shaley limestone. No show. Poor porosity.
3268	3272	Cream medium course crystalline slightly fossiliferous slightly cherty limestone. Very slight trace of stain and very slight trace of free oil. Fair to poor porosity.
3274	3279	Cream medium crystalline dense limestone. Poor scattered stain. Fair to poor porosity.
3281	3286	Cream medium crystalline sucrosic slightly dolomitic limestone. Scattered light stain with trace of free oil. Fair porosity.
3288	3292	Cream fine to medium crystalline sucrosic dolomitic limestone. Fair scattered light stain. Fair porosity.
3292	3296	Hard. Cream dense very cherty w/ gray speckled cherty. No show. Poor porosity.
3296	3301	Med. Hard. Cream dense cherty fossiliferous is scattered. Dead oil stain. Fair to poor porosity.
3301	3307	Med. Soft. Cream to white fossiliferous, fine crystalline, very cherty limestone. Trace of light stain. Fair fossiliferous porosity.
3307	3312	Hard. White cherty limestone. No show. Fair porosity.
3312	3320	Hard. Cream very cherty limestone with tripolitic and sharp angular chert. No show. Poor porosity.
3320	3335	Hard. Cream to light gray medium to coarse crystalline dense very cherty limestone. No show. Poor porosity.
3335	3340	Hard. Cream to light gray medium to coarse crystalline dense very cherty limestone. No show. Poor porosity.
3340	3345	Med Soft. Tan Tripolitic cherty with tan dolomite. Scattered light stain. Fair to good porosity.

RECEIVED
STATE CORPORATION COMMISSION
APR 5 1971
CONSERVATION DIVISION
Wichita, Kansas

3345	3347	Med Hard. Cream to light gray medium to coarse crystalline dense very cherty limestone. No show. Poor porosity.
3347	3350	Hard. Cream to light gray medium to coarse crystalline dense very cherty limestone. No show. Poor porosity.
3350	3355	Hard. Cream to gray tripolitic cherty. Fair, scattered light stain. Fair porosity.
3355	3360	Soft. White and light gray tripolitic chert. Fair, scattered show. Fair porosity.
3360	3367	Hard. Gray speckled sharp angular chert with dense fine crystalline limestone. No show. Poor porosity.
3367	3373	Med soft. Gray speckled sharp angular chert with dense fine crystalline limestone. No show. Poor porosity.
3373	3377	Very hard. Gray speckled sharp angular chert with dense fine crystalline limestone. No show. Poor porosity.
3377	3380	Hard. Gray speckled sharp angular chert with dense fine crystalline limestone. No show. Poor porosity.

Electric Logs: S & B Gamma Ray-Neutron
 DST's: None
 Cores: None

STATE OF OKLAHOMA)
 COUNTY OF TULSA) ss

I, Louis Kahan, Operator, being first duly sworn under oath, say: That I have knowledge of the facts, statements and matters herein contained of the above described well as filed and that the same are true and correct.

 Louis Kahan

Subscribed and sworn to before me this _____ day of _____ 1964.

 Notary Public

My commission expires: May 20, 1966

RECEIVED
 STATE CORPORATION COMMISSION
 APR 5 1971
 CONSERVATION DIVISION
 Wichita, Kansas