

15-079-19054-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Harvey County, Sec. 18 Twp. 23 Rge. 3 W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE SW
Lease Owner K & P Oil Company
Lease Name Sahin Well No. C-3
Office Address P.O. Bx 559 Tulsa, Oklahoma 74101
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed Aug # 19 73
Application for plugging approved Aug # 19 73
Plugging commenced Aug 5 ~~Aug 10~~ 19 73
Plugging completed Sept 19 73
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 3325' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		2,400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3325 to 3250'. Dumped 6 sx of cement. Mudded hole to 290'. Made 15' of rock bridge. Dumped 6 Yrds. of Ready-Mix Cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1973

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Art Lamb*
2809 King St. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 1973

My commission expires January 5, 1974

Judy Lamb
Notary Public.

K & P OIL CO.
 P.O. BOX 632, TULSA, OKLA.
 ZIP 74101

15-079-19054-0000

SUPPLEMENTAL COMPLETION REPORT

Company: K & P Oil Co.
 Para & Well: Sabin C-3, C 3E S1 Sec.18, T-23S, R-3W
 Harvey County, Kansas

Commenced: 11-17-63 Elev.: 1470' KB
 Completed: 12-17-63 Rotary T.D. 3317'
 Initial Potential: 6 H O - 30 B W P D Cable T.D. 3375'

Casing Records:
 10 3/4" @ 266' W/275 sock
 7" @ 3316' W/150 sock

FORMATION TOPS:

Lansing 2537'
 Base of Kansas City 2990'
 Cherokee 3157'
 Mississippi 3272'
 Rotary TD 3317'
 Cable Tool TD 3375'

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 13 1973
 CONSERVATION DIVISION
 Topeka, Kansas

LOG:

0	175	Sand
175	560	Shale
560	2580	Lime Shale
2580	3205	Lime
3205	3285	Lime & Shale
3285	3317	Lime
3317	3321	(Hard). Light gray dense fossiliferous fine crystalline slightly cherty limestone. Fair scattered dark stain. Fair vulgar porosity.
3321	3326	(Hard). Light gray dense fossiliferous fine crystalline slightly cherty limestone. Trace of stain. Poor porosity.
3326	3330	(Medium). Light gray dense cherty fine crystalline limestone. No show. Poor porosity.
3330	3340	(Medium). Light gray dense cherty limestone. Trace of dark stain. Poor porosity.
3340	3350	(Hard). Light gray dense cherty limestone. Very slight trace of stain. Poor porosity.
3350	3355	(Soft) White tripolitic chert and tan fine crystalline limestone. Fair scattered dark stain. Trace of saturation. Fair porosity.
3355	3358	White tripolitic chert and dense limestone. No show. Poor porosity.
3358	3368	(Medium). Light gray very cherty fossiliferous limestone, w/dolomitic limestone and tripolitic chert. Scattered stain. Fair porosity.
3368	3375	White bone and tripolitic chert. Acidize w/500 gal. of 15% regular acid. POP

Electric Surveys: S.E.B Gamma Ray-Neutron
 DST: None
 Core: None

Continued on Page 2

STATE OF OKLAHOMA)
COUNTY OF TULSA) ss

I, Louis Kahan, Operator, being first duly sworn under oath, say: That I have knowledge of the facts, statements, and matters herein contained of the above described well as filed and that the same are true and correct.

LOUIS KAHAN

Subscribed and sworn to before me this _____ day of January, 1964.

NOTARY PUBLIC

My commission expires: May 20, 1966.