


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD 15-079-19040.0000

Harvey County, Sec. 18, Twp. 23, Rge. 3W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner H.C. Bennett
Lease Name Hurty Well No. 2
Office Address 1212 Union Nat'l Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 10-16-48 19
Application for plugging filed 10-23-67 19
Application for plugging approved 10-24-67 19
Plugging commenced 10-25-67 19
Plugging completed 10-27-67 19
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3387 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	240'	none
				5 1/2	3351'	2500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with sand from 3387' to 3350' and dump 5 sacks of cement

Set 10' rock bridge from 260' to 250' and dump 25 sacks of cement

Mud hole to 40', rock to 30' and dump 10 sacks of cement to surface

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Kenneth Smith*

(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of November 19 67

Sept. 19, 1971

Jeanne D. Davis

Notary Public.



KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COPY

GP

COMPANY H.C. BENNETT

SEC. 18 T. 23 R. 3W

FARM Hurty

NO. 2

LOC. C NW NW


15-079-19040-0000

TOTAL DEPTH 3387'

COUNTY Harvey

CDMM. 10-2-48

COMP. 10-16-48



SHOT OR TREATED

CONTRACTOR

ISSUED 2-19-48

CASING

20	10	
15	8 5/8	240' w/225 sx cem.
12	6	
13	5 1/2	3351' w/40 sx cem.

ELEVATION

PRODUCTION 15 Bbbls/d

sand, clay	105
sand, clay, shells	185
clay	215
clay sand	230
clay, shells	239
clay	500
anhydrite	590
shale, shells	665
shale, lime	840
lime	1020
shale, shells	1160
shale, lime	1480
shale, shells	1625
shale, lime	1890
lime	2015
lime, shale	2170
shale	2300
shale, lime	2540
lime	2590
lime, shale	2720
lime	3265
shale	3300
Mississippi lime	3345
dolomite zone	3387
Total Depth	

FIGURES INDICATE BOTTOM OF FORMATIONS

TOPS:
 Mississippi lime 2345

RECEIVED
 STATE CORPORATION COMMISSION

OCT 25 1951

CONSERVATION DIVISION
 Wichita, Kansas

Keep this for future.