

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-079-00532-0000

API NUMBER None

LEASE NAME Wiley

WELL NUMBER 3

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 18 TWP. 23S RGE. 3 ~~(28)~~ or ~~(4)~~

COUNTY Harvey

Date Well Completed 11/5/48

Plugging Commenced 2/12/92

Plugging Completed 2/18/92

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Johnny Sanders (KCC District Agent's Name).

Is ACO-1 filed? On old form if not, is well log attached?

Producing Formation Mississippi Depth to Top 3308 Bottom 3358 T.D. 3358

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Oil	3308	58	8 5/8	272	-0-
				5 1/2	3308	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spotted 35 sxs 60/40 poz + 4% gel thru 2 3/8" tbg on bottom. Shot hole in 5 1/2" @ 340'. Pumped 100 sxs 60/40 poz and displaced to 350'. Top of cement @ 286'. Pumped 50 sxs 60/40 poz down annulus and circ'd. Shot hole in 5 1/2" @ 257'. Pumped 150 sxs 60/40 poz. Tag cmt @ 70'. Cmt'd to surface w/l yd. ready-mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company **MAR - 2 1992**

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

MELISSA A MCWHIRT  
Notary Public-Oklahoma  
TULSA COUNTY SUBSCRIBED  
My Commission Expires  
March 21, 1994

AND SWORN TO before me this 28th day of February, 19 92

Melissa A. McWhirt  
Notary Public

My Commission Expires: March 21, 1994

KANSAS WEATHER BUREAU -- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

15-079-00532-0000

COMPANY SIMON LEBOW et al  
FARM Wiley NO. 3

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 18 1991  
COUNTY Harvey  
KANSAS

TOTAL DEPTH 3337  
COMM. 10-20-48  
SHOT OR TREATED  
CONTRACTOR  
ISSUED 2-4-50  
COMP. 11-5-40

DEC 18 1991  
COUNTY Harvey  
KANSAS  
CONSERVATION DIVISION  
WICHITA, KANSAS


CASING  
20 10  
15 8 272'  
12 6  
13 5 1/2 3308'

ELEVATION

PRODUCTION Pot. 100 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil & sand	261
shale & shells	273
shale & lime shells	355
shale & shells	465
gyp rock	490
lime	570
lime & shale shells	790
lime & shale	850
sand	900
lime & shale	1586
shale & lime shells	1650
lime & shale	1820
lime	1875
shale	2020
lime	2090
shale	2155
shale, lime & shells	2260
shale & lime	2400
shale, lime & shells	2495
lime & shale	2540
shale & lime	2685
lime	2825
shale	2855
lime	2920
lime & shale	3000
shale & lime shells	3080
shale & lime	3125
lime & shale	3210
shale	3280
mississippi lime	3305
lime	3337
lime	3358
Total Depth	