

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-079-00531-0001

API NUMBER None

LEASE NAME WILEY

WELL NUMBER 2

3630 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 18 TWP. 23S RGE. 3 (E or W)

COUNTY Harvey

Date Well Completed 10/19/48

Plugging Commenced 12/27/85

Plugging Completed 1/9/86

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 2, Wichita, KS

Is ACO-1 filed? on old form if not, is well log attached? ---

Producing Formation None Depth to Top --- Bottom --- T.O. 3358

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Miss	N/A	3310	58	8-5/8	263	None
				5-1/2	3310	186

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged bottom with sand to 3260' & 6 sacks cement. Shot pipe at 2325' & 2115'. Pipe parted, Pulled 6 joints of pipe. Plugged well with 3 hulls, 15 gel & 115 sacks cement.

PLUGGING COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, KS 67524

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1986

[Signature]

My Commission Expires: 2/11/89

Notary Public  
RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1986

Form CP-4  
Revised 08-84

WELL LOC. 60-310 KANSAS GEOLOGICAL SOCIETY  
 508 E. MURDOCK, Wichita, Kansas

15-679-00531-0000


Company SIRON LEBON ET AL.  
 Farm Wiley No. 2

SEC. 18 T. 23 R. 4W  
 ON/2 SE-NE

County Harvey

KANSAS

Total Depth 3358  
 Comm. 10-9-48 Comp. 10-19-48  
 Shot or Treated  
 Contractor  
 Issued 2-4-50



CASING:

8 5/8" 261 surface cem.  
 5 1/2" 3335 cem.

Elevation \_\_\_\_\_

Production Est. 75 bbls.

Figures Indicate Bottom of Formations.

surface soil & sand	10
sand	250
shale	280
shale river gravel	305
shale shells	460
anhyd.	500
lime brkn	695
lime, shells & shale	835
salt	880
lime & shale	1285
lime, shells & shale	1425
lime shale	1600
shale	1815
lime	2025
lime, shells & shale	2195
lime & shale	2310
shell & lime shells	2530
lime & shale strks	2680
shale	2695
lime	2730
shale	2910
lime & shale	2950
shale	2980
shale & lime strks	3065
lime & shale	3210
shale	3275
misc. lime	3335
lime	3358
Total Depth	

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 18 1935

CONSERVATION DIVISION  
 Wichita, Kansas