


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit.  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Harvey County, Sec. 31 Twp. 23S Rge. 3W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Tomlinson-Kathol, Inc.  
Lease Name Base Well No. 3  
Office Address 1125 Wichita Plaza Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-18-67 19  
Application for plugging filed 10-18-67 19  
Application for plugging approved 10-18-67 19  
Plugging commenced 10-18-67 19  
Plugging completed 10-18-67 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, McPherson, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3400 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 210' - plug - 30 sks. cement through drill pipe  
Mud to 35' - 1/2 sk. hulls, plug & 15 sks. cement

STATE CORPORATION COMMISSION

OCT 20 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 19 67

My commission expires April 1, 1971

Ulanda Nichols  
Notary Public.

DRILLER'S LOG

15-079-2003Z-000

COMPANY: Tomlinson-Kathol, Inc.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: BASE #3  
 LOCATION: SE SE SW SECTION 31-23S-3W  
 HARVEY COUNTY, KANSAS  
 COMMENCED: 10-11-67  
 COMPLETED: 10-18-67

0	20	Clay, Sand
20	185	Sand, Shale
185	220	Shale
220	480	Shale, Shells
480	1090	Lime, Shale
1090	2275	Shale, Lime
2275	2565	Lime, Shale
2565	2645	Shale
2645	2830	Lime, Shale
2830	3240	Lime
3240	3383	Shale, Lime
3383	3400	Mississippi
	<u>3400</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 20 1967  
 CONSERVATION DIVISION  
 Wichita, Kansas

10 3/4" 32# surface casing set @ 215' cemented with 275 sacks of  
 Common, 2% cc, 2% gel

I, Leslie Kite, do hereby certify that the above and foregoing is  
 a true and correct copy of the log of the Base #3 Well, located SE  
 SE SW of Section 31, Township 23 South, Range 3 West, Harvey County,  
 Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in  
 and for Barton County, Kansas; this 19th day of October, 1967.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires:  
 April 1, 1971