


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-079-19130-0000 Form CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Harvey County, Sec. 11 Twp. 23 Rge. 3 W (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner Home Stake Production Company
Lease Name Brillhart "B" Well No. W-42
Office Address Burrton, Kansas 67020
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/24/68 19
Plugging completed 6/25/68 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation Depth to top Bottom Total Depth of Well 3365 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	513'	none
				4 1/2"	3339'	2432'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3365', ran sand to 3330' and dumped 4 sacks of cement. Loaded hole, shot pipe at 2445', worked pipe loose and pulled 77 joints. Set rock bridge from 310 to 300' and dumped 35 sacks of cement. Mudded hole to 40', set 10' rock bridge and dumped 15 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

Subscribed and sworn to before me this 26 day of June, 1968

My commission expires February 15, 1971

Notary Public.

SP

Farm Name: Brilhart "B" Well Number: W-42
In the: Burrton Waterflood Project Character of Well: WATER INPUT
Located in: Harvey County, Kansas Section 31 Twn. 23S Range 3W
Well Spot: NW/4

1150' East of West line and 1270' South of North line.

Ground Elevation: 1455' K. B. Elevation: 1460'
Drilling Started: July 8, 1963 NOTE: All measurements are from the K. B.
Drilling Completed: July 15, 1963 Well Completed: November, 1963
DATE OF FIRST PRODUCTION: - - DATE OF FIRST INJECTION: November 5, 1963

Casing Record: Set at 513' - 10-3/4", 40#, Used, surface casing.
Set at 3339' - 4-1/2", 9.5#, New casing.

Cementing Record: 400 sacks common cement w/2% gel and 2% CC added for surf. casing.
150 sacks of common cement for the long string.
Cement was circulated.

Fracture or Shot Record: Acidized with 500 gallons 15% regular acid.
EFFECTIVE PAY ZONE: MISSISSIPPI (Tripolitic) CHAT

PERFORATED: None - open hole. No. of Shots _____
No. of Shots _____
No. of Shots _____
No. of Shots _____
No. of Shots _____
Total number of holes _____

FORMATION RECORD

Rotary drilled: Surface to 3348'
Cable tools: 3348' to 3365'

	Top	Bottom	Top	Bottom
Sand and shale	-0-	180		
Shale	180	465		
Anhydrite lime	465	515		
Lime and shale	515	1055		
Shale and shells	1055	1650		
Shale and lime	1650	1975		
Shale and shells	1975	2490		
Shaley lime	2490	2532		
Top of Lansing-Kansas City	2532			
Lime w/small shale breaks	2532	3158		
Shaley lime and shale	3158	3269		
Top of Mississippi	3269			
Lime	3269	3336		
MISSISSIPPI (Tripolitic)				
CHAT	3336	3365		
Total Depth	3365'			

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1968
CONSERVATION DIVISION
Wichita, Kansas

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct & complete according to our records and to the best of my belief and knowledge.

Robert O. Kline Engineer
Name and title of representative of company

Subscribed and sworn to before me this 17 day of December, 1963

My Commission expires January 29, 1967

Leis M. Nicklaus
Notary Public