


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD 15-079-19128-0000

NORTH



Locate well correctly on above
Section Plat

Harvey County, Sec. 31 Twp. 23 Rge. 3 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner Home Stake Production Company
Lease Name Brillhart Well No. A#1
Office Address Burrton, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/28/68 19
Plugging completed 7/ 5/68 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3362 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	280'	none
				6-5/8"	3269'	HEMM 2323'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3362', ran sand to 3260' and dumped 7 sacks of cement. Loaded hole, shot pipe at 2442', 2335', pulled 82 joints. Set rock bridge at 280' to 270' and ran 35 sacks of cement. Mudded up and ran 15 sacks of cement on top.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 8th day of July, 1968

My commission expires February 15, 1971

Notary Public.

COPY

THE PALMER OIL CORP.

Brilhart No. 1.

BRILHART "A"

Total Depth. 3392'

Cora. 8-21-37 Comp. 8-11-37

Shot or Treated.

Contractor. Palmer Oil Corp.

Issued. 10-2-37

SEC. 31. R. 23. S. 37

NE 1/4 NW

15-079-19128-0000

County. Harvey



CASING:

10" 980

2 5/8" 3359'6"

2 1/2" 3359'6"

Elevation.

1458.1 GL.

Production. Pot. 1233 B.

Figures Indicate Bottom of Formation.

sand & shells	256
shale & shells	266
shale	450
lime brkn	560
shells & shale	820
brkn lime	950
lime	925
brkn lime & shale	1058
lime	1075
lime & shale	1180
brkn lime	1290
shells & shale	1395
lime & shale	1520
shells & shale	1655
shale & lime	1765
shale & shells	1860
brkn lime	1940
shells & shale	2020
shale & brkn lime	2105
brkn lime	2320
lime	2380
brkn lime	2470
shells & shale	2414
lime, shale & lime brd	2515
lime	2610
brkn lime	2695
lime	3155
shale & lime	3225
shale & shells	3270
chert	3278

Drilling gas 3382

Show oil 3300-05

shat 3362

oil 3355-3382

Total Depth.

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1938
CONSERVATION DIVISION
Wichita, Kansas

9-12-37
T & 3270 (37)
TD 3362
IP 1233

Top 3270
1458
-1812

TD 3362
Top 3270
92'

TD 3362
1458
-1904

oil 3355-62
1458
-1903

sh 3300
1458
-1848

Set 6 5/8 at 3259

Simples indicate 35' from First Show.

as noted