

KANSAS

*M*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name S & K Oil Company 15-15 20014-0000

Complete Address: Box 682 Tulsa, Oklahoma 74101

Lease Name Sabin "B" Well No. # 6

Location SW SW SW Sec. 13 Twp. 23 Rge. 4 (E) (W)

County Reno Total Depth 3354'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Bert Self

Address: Hutchinson, Kansas License No. # 48

Operation Completed: Hour 11 AM Day 10 Month 8 Year 68

The Above well was plugged as follows:

10 3/4"-157'-Circulated w/cement. 5 1/2"-3327'-Cemented. Sand hole to 3325'.

5 Sax.cement 3325' to 3275'. Mud 3275' to 170'. Bridge 170' to 160'.

35 Sax.cement 160' to 90'. Mud 90' to 40'. Bridge 40' to 30'.

15 Sax.cement 30' to 0. Pulled 2400'-5 1/2"-pipe.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8/12/68  
INV. NO. 8253-W

Signed: *Hughes*  
Well Plugging Supervisor