

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1969
CONSERVATION DIVISION
Wichita, Kansas

15-155-20107-6000

Operator's Full Name R.L. Evans

Complete Address: R.R. Hutchinson, Kansas 67501

Lease Name Evans Well No. # 9

Location SE SW NE Sec. 23 Twp. 23 Rge. 4 (E) (W)

County Reno Total Depth 3360'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co. Inc.

Address: Chase, Kansas License No. # 624

Operation Completed: Hour 4 PM Day 29 Month 8 Year 69

The Above well was plugged as follows:

10 3/4"-256'-Circulated w/cement. 8 5/8"-555'-No Cement 5 1/2"-3221'-Cemented.
Sand hole to 3200'. 5 Sax.cement 3200' to 3150'. Mud 3150' to 270'.
Bridge 270' to 260'. 35 Sax.cement 260' to 200'. Mud 200' to 40'.
Bridge 40' to 30'. 15 Sax.cement 30' to 0.
Pulled 2766'-5 1/2"-pipe. Pulled 331'-8 5/8"-Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed Hugh Scott
Well Plugging Supervisor

DATE 9/2/69
INV. NO. 392-w