

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR  
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Reno County. Sec. 23 Twp. 23 S. Rge. 4 W. ~~4 E~~ NW 1/4 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C.N.E. NE  
Lease Owner Olson Drilling Company  
Lease Name F. Duckworth Well No. 2  
Office Address Petroleum Bldg., Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed unknown 19  
Application for plugging filed September 1946  
Application for plugging approved October 1946  
Plugging commenced October 1946  
Plugging completed October 1946  
Reason for abandonment of well or producing formation dry  
If a producing well is abandoned, date of last production unknown 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Mr. Raul Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3284' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				16"	255'	none
				8-5/8"	3284'	2750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 8 sacks of cement in bottom of hole.  
Shot pipe off at 2750'. Mudded hole and put cement bridge at 300';  
then mudded surface pipe and put cement plug at top of surface.

FILE 23 23 46  
BOOK PAGE 70 OF 30

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Herman Kaiser Pipe & Supply Company  
Address 916 Palace Bldg., Tulsa, Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
Berthold Neuwald (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Berthold Neuwald

916 Palace Bldg., Tulsa, Okla. 11-23-46  
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of November, 1946

Alfred [Signature] Notary Public.

My commission expires My Commission Expires Nov. 3, 1950

15-15-36267-0000

DLDG.  
OLSON ~~XXX~~ COMPANY  
F. DUCKWORTH #2  
C NE NE 23 23S 4W  
RENO COUNTY, KANSAS.

COMMENCED 7-10-34  
COMPLETED 11-21-34  
ELEVATION 1466'  
I.P. 28,000,000 Cu.Ft.

CASING RECORD

12 1/2" 70# 253'  
8 8/5" 32# 3266'  
8 5/8" Cem W/ 250 Sac. Cem.

0  
125--Sand  
85-- " & shale  
255--Shale  
445-- " & shells  
70--Salt  
796--Shale & shells  
885--Lime  
915--Shale & shells  
98-- " Lime  
1010--Lime  
1286--Shale & shells  
1445-- "  
1591-- " "  
1623--Lime  
1714--Shale & shells  
24--Lime  
54--Shale  
1952-- " "  
99--Broken lime  
2124--Lime  
55--Broken lime  
2211--Lime ash  
2332--Broken lime  
2500--Shale & shells  
98--Broken lime  
2616--Lime  
2697--Broken Lime  
2710--Lime  
30--Broken lime  
36--Lime  
64-- " & shale  
2817-- "  
30-- " ash  
2904-- "  
9-- " Oolitic  
59-- "  
3030--Broken lime  
50--Lime  
98-- " & shale  
3251--Var. Lime  
67--Chat, R.u.s.t.  
90-- " gas 5500 M  
3300-- " " 7500 M  
3325-- " " 28000 M  
T.D.

23 23 4W  
70 35

