

15-155-30156-0000

API NUMBER C-13167

LEASE NAME EVANS B

WELL NUMBER SWD # 5

460 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 23 TWP. 23 RGE. 4 (E) or (W)

COUNTY Reno

Date Well Completed 1-11-67

Plugging Commenced 11-5-87

Plugging Completed 11-6-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Plains Oil

ADDRESS 5510 E-17 Hutchinson, Ks

PHONE# (316) 662-1515 OPERATORS LICENSE NO. 9246

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on ON file 4-30-1986 (date)

by WARREN Kneipatrick (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 3334

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	244	10 3/4	1-2-67	No.
		Surface	585	8 5/8	1-5-67	No.
		Surface	3331	5 1/2	1-11-67	Down hole 275 To 3334 (Left in hole) Cemented full

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 300 sacks cement with 7 sacks CC between the 8 5/8 pipe and the 10 3/4 on 11-5-87 - shut down until 9:00 on 11-6-87 - Pumped 35 sacks 60/100 with 2 sacks and got cement to surface. Pumped 25 sacks gel, 1 sack shells and 45 sacks 2 1/2 down 8 5/8 pipe - pressure to 350 lbs.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor United Cementing Co License No. _____

Address 2510 West 6th El Dorado, Kansas

STATE OF KANSAS COUNTY OF Reno, ss.

Richard L Gagnebin (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Richard L. Gagnebin

(Address) Hutchinson Ks 67501

SUBSCRIBED AND SWORN TO before me this 19 day of January, 19 88

Charles Hoffman 1-20-88

Notary Public



Commission Expires: 10-31-1990

CONSERVATION DIVISION
 Wichita, Kansas