


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 23 Twp. 23 Rge. 4 (E) X (W)
Location as "NE/CNW/SW" or footage from lines. C of E/2 of E/2 NE
Lease Owner Tomlinson-Kathol Inc.
Lease Name Evans Well No. #4
Office Address 1125 Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 9-18-67 19
Application for plugging approved 19
Plugging commenced 9-18-67 19
Plugging completed 9-22-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3349' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3290'	2720.64'
				8 5/8"	532'	392.79'
				10 3/4"	230'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3280', mixed and ran 5 sacks cement thru dump bailer.
Mudded hole to 210', set 10' rock bridge. Mixed and ran 25 sacks cement thru dump bailer. Mudded hole to 40', set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of September, 1967

My commission expires 24 October 1968
Sidney D. Miller
Notary Public.

15-155-30155-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
509 EAST MURDOCK WICHITA, KANSAS

COPY

COMPANY SeRoBee-Evans

SEC. 23 T. 23 R. 4W

FARM Evans

NO. 4


LOC. C E/2 E/2 NE/4

TOTAL DEPTH 3334'
COMM. 12-6-66

COMP. 12-16-66

COUNTY Reno

SHOT OR TREATED
CONTRACTOR SeRoBee Drilling Co., Inc.



ISSUED 3-11-67

CASING

20	10	3/4" - 252' W/250 sx
15	8	5/8" - 532' W/75 sx
12	6	
13	5	1/2" - 3291' W/75 sx

ELEVATION 1464 DF

PRODUCTION PMP 25 BOPD
& WTR.

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 252	Sand & Shale
252 - 500	Shale & Lime
500 - 850	Lime
850 - 900	Shale & Lime
900 - 10000	Lime
1000 - 1035	Shale & Lime
1035 - 1515	Shale & Shells
1515 - 2730	Shale & Lime
2730 - 3076	Lime
3076 - 3249	Shale & Lime
3249 - 3334	Miss. Lime - T. D.

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1967

CONSERVATION DIVISION
Wichita, Kansas

GEOLOGICAL TOPS:

K. C.	
K. C.	2756
Bs/KC	2986
Cherokee	3147
Miss.	3258

I certify the above to be a true and correct copy of the driller's log ~~book~~ and the geological tops to the best of my knowledge and belief.

Paul S. Septer

Paul S. Septer