

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-155-2087-00-01
API NUMBER Spud 12/22/71

LEASE NAME Vansickle

WELL NUMBER #6

1280 Ft. from N Section Line

330 Ft. from W Section Line

SEC. 23 TWP. 23S RGE. 4W (E) or (W)

COUNTY Reno

Date Well Completed 1/72

Plugging Commenced 2/15/95

Plugging Completed 2/16/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Producers Oil Company

ADDRESS 427 S. Boston, STE 711, Tulsa, OK 74103-4199

PHONE#(918) 582-1188 OPERATORS LICENSE NO. 5235

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/95 (date)

by Micheal R. Wilson (KCC District Agent's Name).

Is ACO-1 filed? NA If not, is well log attached? NA

3284 Miss. 3380
Producing Formation Miss. & Hunton Depth to Top 3610 Hunton Bottom 3615 T.D. 3615

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Hunton	Oil	3610	3615	10 3/4	241'	0
Miss.	Oil & water	3323	3380	5 1/2	3610'	0
Miss.	Tr. Gas	3284	3290			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 3270 & capped w/2 sx. cement, perf. 5 1/2 @ 615', ran tbg. to 615 & spotted 35 sx. 60/40 poz. plug, perf. 5 1/2 @ 375, ran tbg. to 339', spot 177 sx. 60/40 poz. tag cement inside 5 1/2 @ 344 and outside at 375, ran 1" tbg. on outside of 5 1/2 to 375, pump 151 sx. 60/40 poz. circulate to surface, ran 1" inside 5 1/2 to 344', pump 40 sx., circ. to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sunflower Well Service License No. 30280

Address 408 North 4th, P.O. Box 341, Canton, KS 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Producers Oil Company

STATE OF Oklahoma COUNTY OF Tulsa

Phillip W. Terry (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Phillip W. Terry

(Address) 427 S. Boston, STE 711, Tulsa, OK

SUBSCRIBED AND SWORN TO before me this 9th day of March, 19 95

Notary Public

My Commission Expires: 8-7-96