


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-155-20087-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

RENO County. Sec. 23 Twp. 235 Rge. 4W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
Lease Owner 5/2 SW/4 NE/4  
Lease Name HAROLD J. MILBURN Well No. 8  
Office Address 7315 N. MONROE HUTCHINSON, KS. 67501  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Date Well completed 12-15 1978  
Application for plugging filed 6-4 1979  
Application for plugging approved 6-5 1979  
Plugging commenced 8-20 1979  
Plugging completed 8-23 1979  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert TAMAN  
Producing formation \_\_\_\_\_ Depth to top 3319' Bottom 3325' Total Depth of Well 3325'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	250'	- 0 -
				8 3/8"	578'	- 0 -
				5 1/2"	3319'	2666.30'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

8-20-79 Drove to lease, Rigged up Unit-floor-Jacks-  
Targued up pipe. Filled up with sand to 3300' dumped five sacks Cement.  
8-21-79 Ripped pipe at 2800' + 2666'. Pulled 5 1/2" pipe out. 8-22-79 Rigged  
up 8 3/8" Equipment. Welder cut 8 3/8" loose from 13" took strain shot 8 3/8" casing  
2 times at 3317' could not get loose. 8-23-79 Shot casing two more times.  
1st at 3317' + 200 would not come loose. Set top plug at 265' with 10' rock  
bridge. Rigged down Equipment + loaded it. Filled to top with ready mix.  
Rigged unit down.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor TOWANDA Well Service INC.

STATE OF KANSAS COUNTY OF Butler, ss.  
George Keith (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Lewis C. Wilson  
608 MAIN, TOWANDA, KS. 67144  
(Address)

SUBSCRIBED AND SWORN TO before me this 24<sup>th</sup> day of Aug., 19 79


Robert G. Simmons  
Notary Public.

My commission expires July 17, 1980

RECEIVED  
STATE CORPORATION COMMISSION

AUG 27 1979

CONSERVATION DIVISION  
Wichita, Kansas



# Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS  
67460

December 17, 1968

15-155-20087-0000

COMPANY: R. L. EVANS  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: EVANS # 81  
 LOCATION: S/2 SW/4 NE/4, Sec. 23-23-4W,  
 Reno County, Kansas  
 COMMENCED: December 7, 1968  
 COMPLETED: December 15, 1968  
 ELEVATION:

0	to	230	Sand
230	to	250	Shale
250	to	828	Shale & Shells
828	to	1134	Shale & Lime
1134	to	1230	Lime & Shale
1230	to	2025	Shale & Lime
2025	to	2245	Lime
2245	to	2525	Lime & Shale
2525	to	3260	Lime
3260	to	3325	Mississippi
		3325	T. D.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN - 5 1979  
 CONSERVATION DIVISION  
 Wichita, Kansas

17 inch hole  
 Cut to 250 ft. and run 252 ft. of 1 1/2 in. surface pipe, cemented with 225 sacks on bottom at 250 ft., Plug down at 2:00 P.M., December 7, 1968. Reamed 11 inch hole to 578 ft., run 603.61 ft. of 8 5/8 in surface pipe, cemented on bottom at 578 ft. with 100 sacks cement. Plug down at 3:00 P.M., December 11, 1968. Cut 7 7/8 in. hole to 3825 ft., and run 3239.95 ft. of 5 1/2 in. casing and cemented with 75 sacks salt saturated Pozmix six foot off bottom at 3319 ft. Plug down at 3:00 P.M., December 15, 1968.

TOPS: Mississippi - 3260'

Measurements taken from K.B.

### CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Evans #8, located on the S/2 SW/4 NE/4 of Sec. 23-23-4W, Reno County, Kansas as reflected by the files of the BLACKSTONE DRILLING, INC.

H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 17th day of December 1968.

Ruth McVay - Notary Public



My Commission Expires: 12/19/1969.