

15-155-02566-0000  
✓ P. 10

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division,  
State Corporation Commission,  
800 Bittling Building  
Wichita, Kansas

**RECEIVED**  
JUL 29 1935  
me.

OR  
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Reno County, Sec. 23 Twp. 23 Rge. (E) 4 (W)

Lease Name: S. E. Vansickle Well # 5 SE SW NW  
Lease Owner: Marathon Oil Company  
Office Address: Box 86, Wichita, Kansas.  
Character of Well (Oil, Gas or Dry): Gas Total Depth of Well: 3875 Feet  
Date, well, completed: July 9 1935  
Application for plugging and log of well filed: June 19 1935  
Application for plugging approved: 1935  
Plugging Commenced: June 25 1935  
Plugging Completed: July 9 1935  
Reason for abandonment of well or producing formation: No production under 3335'

NORTH


Locate well correctly on above 640 A. Plat

If a producing well is abandoned, date of last production: 1935

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Officer who supervised plugging of this well: None

Producing formation: Chat Depth to top: 3250 Bottom: 3335

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Shale, Lime & sand	Water	3796	3813	5 3/16	3613	3423
Sand	Water	3762	3796	7	3335	3335
Sand	Water	3624	3652	8 5/8	3270	
Hunton Lime	Water	3613	3624	1 1/2	218	
Sand	Water	3370	3375			
Chat	Gas	3303	3326			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Cement placed in hole with dump bailer from 3875' to 3632'. Lead wool drove from 3632 to 3631. 3631 to 3617' plugged with rock. 3617' to 3614' with lead wool. Cement, rock and lead wool from 3614 to 3335'.

Well is now producing gas from 3303' to 3326'. Water entirely shut off

**PLUGGING**  
FILE SEC 23 TWP 23 R 4  
BOOK PAGE 6 LINE 30

Log of well was mailed to your office on June 19th.

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? Yes

Was exception made? No If so describe

Correspondence regarding this well should be addressed to Marathon Oil Company

Address: Box 86, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Bruce Aug

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce Aug

Box 818, 911 Phoenix Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July 1935.

My commission expires Feb. 11, 1937.

A. J. McClintock

Notary Public.

15-155-02566-0000




# MARATHON OIL COMPANY

GENERAL OFFICES

~~WICHITA, KANSAS~~


PO BOX 281



Box ~~281~~  
Wichita, Kansas,  
June 19, 1935.

*Pamphlet to be  
sent to Alexander*

Mr. T. A. Morgan,  
State Corporation Commission,  
800 Bitting Building,  
Wichita, Kansas.



Dear Sir:

We have completed S. E. Vansickle No. 5, located in SE Corner SW $\frac{1}{4}$  NW $\frac{1}{4}$  23-23-4 West, Reno County, drilling it to 3875', Top Siliceous 3855'. We are plugging this well back to the chat to produce the gas in the chat. The well will be cemented in accordance with the rules and regulations of the commission to shut off the water, which will be to our interest. I am enclosing copy of the log.

Yours truly,

HMW:M  
enc



**PLUGGING**  
FILE SEC 23-23-4W T R  
BOOK PAGE 6 LINE 29

15-155-62566-0000

June 20, 1935. Plugging back S.E. Vansickle  
No. 5  
SE Cor. SW NW 23-23-4W  
Reno County  
6-29

Marathon Oil Co.,  
Tulsa, Oklahoma,

Attention: Mr. E. H. Williams

Dear Sirs:

This letter is your permission to plug back the above subject well to the chat, in accordance with the rules and regulations of the Kansas State Corporation Commission.

Yours very truly,

T. A. MORGAN, Director

TC:ha

By

(c. c.--C. T. Alexander

MARATHON OIL CO

LOG

S E VANSICKLE # 5  
SE SW NW 1/4 23-23-4 W Reno County

15-155-02566-0000

Casing Record:

15 1/2" - 222  
6 5/8" - 3335  
5 3/16" - 3613

PLUGGING  
FILE SEC 23 T 23 R 4W  
BOOK PAGE 6 LINE 79

shale shells 970  
lime 1000  
shale shells 1525  
lime 1545  
shale shells 1931  
shale & lime 2342  
sand shale lime 2410  
lime & shale 2540  
lime 2955  
shale 3265  
chat & lime 3495

Top chat 3265  
1st gas 3303  
3319-26 8 1/2 M.  
1st oil 3346  
inc. to 3365 more 3365-68

shale 3602  
sdy shale 3608  
sand 3610  
shale 3613

Top Hunton 3613  
6 BW 3627

lime 3624  
sand 3635  
lime 3638  
sand 3652  
sdy lime 3659  
lime 3694  
shale 3695  
lime 3701  
shale 3728  
sdy shale 3739  
lime 3747  
shale & lime 3754  
lime hard 3762  
sand 3790  
sand 3796  
Wilcox sand 3813  
shale & lime 3822  
lime sdy 3830  
shale & lime 3842  
lime 3846  
lime broken 3855  
green shale & sand wtr 3860  
lime 3875

Top Viola 3739

Top Wilcox 3772  
Top Siliceous 3855

T.D.

Plug back to chat to save chat gas