

**Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas**

**OR**

**Strike out upper line when reporting plugging off formations.**

RENO

County. Sec. 23 Twp. 23S Rge.        (E) 4 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines..... NW NW NE/4

Lease Owner.....Olson Oil Co.

Lease Name F. Duckworth Well No. 3

Office Address Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date, well completed..... 3 - 13 - 19 35

Application for plugging filed..... 8 - 6 -19 ~~41~~

Application for plugging approved..... 8 - 8 -19 41

Plugging Commenced..... 8 - 11- 1941

Plugging Completed..... 8 - 22 - 19 41

Reason for abandonment of well or producing formation..... Well went dry.

---

If a producing well is abandoned, date of last production..... Test 7 - 17- 19 41

Was permission obtained from the Conservation Division or its agents before plugging was com-

menced?.....Yes.....

ed plugging of this well..... **Ruel Durkee**

..... Depth to top **3318** ..... Bottom **3372** ..... Total Depth of Well **3404** ..... Feet

and gas formations.

OIL, GAS OR WATER RECORDS

## CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from .....feet to .....feet for each plug set.

Filled hole from total depth with chat and 10 sacks of cement to 3404. (Ripped 7" from 3318 to 3372.) Mudded hole from 3404 to 3310. Dumped 6 sacks of cement at 3310. Mudded hole to 700 ft. Dumped 15 sacks of cement at 700 ft. Mudded hole to 140ft. dumped in 5 ft of rock to 135 ft. Dumped 30 sacks of cement at 135 ft. Mudded hole to 8 ft. and dumped 15 sacks of cement at base of cellar.

(If additional description is necessary, use **BACK** of this sheet)

Correspondence regarding this well should be addressed to..... S. A. Keefover

Address.....Box R.....Burrton, Kansas

STATE OF KANSAS, COUNTY OF RENO

S. A. Keefover

(employee of owner) or (~~owner or operator~~) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature).

(Address)

SUBSCRIBED AND SWORN to before me this 27 day of August, 1941

My commission expires \_\_\_\_\_

OLSON OIL COMPANY  
F. DUCKWORTH # 3  
NW NW NE 23-23-S-4W  
RENO COUNTY, KANSAS

COMMENCED 1- 3-35  
COMPLETED 3-13-35  
ELEVATION 1468



15-155.62559-0000

0  
128 Sand  
165 "  
185 Clay  
255 Sh & lime shells  
470 Shale  
482 Shale & lime shells  
522 Lime & shale  
580 Shale  
590 Lime  
683 Shale & lime shells  
704 Shale  
810 Shale & lime  
975 Sh & lime shells  
1000 Lime & shale  
08 Red rock  
1150 Broken lime  
1353 Shale & lime shells  
70 Broken lime  
1490 Sh & lime shells  
1570 Shale  
1610 Broken lime  
1720 Sh & lime shells  
45 Shale  
53 Broken lime  
1806 Shale  
81 Broken lime  
2026 Sh & lime shells  
41 Broken lime  
88 Lime  
2116 Broken lime  
53 Lime  
2200 Broken lime  
16 Lime  
2270 Broken lime  
88 Lime  
2418 Broken lime  
33 Lime  
71 Sand  
81 Shale  
2512 Sh & lime shells  
45 " " "  
75 Lime  
88 Broken lime  
2605 Lime  
92 Broken lime

2709 Lime  
64 Broken lime  
2804 Lime  
19 Broken lim  
92 Lime  
2904 Lime, oolitic  
66 Lime  
3009 Broken lime  
69 " "  
3152 Sh & lime shells  
3224 Shale  
50 Var. Shale  
3409 Chat  
81 Lime  
3587 Lime  
88 Lime, R.U.S.T.  
3606 Lime, Total Depth  
H. F. O.

CASING RECORD

15 $\frac{1}{2}$ "	70#	10 thd.	LW	255
12 $\frac{1}{2}$ "	50#	8 "	LW	490
10 $\frac{3}{4}$ "	40	8 "	LW	711
7 "	22#	10 "	SS	3587



Subscribed and sworn to before me  
this 27th day of August, 1941

G. I. Bryant  
Notary Public

I hereby certify that the above is  
a true and correct copy of the log of  
F. Duckworth # 3, NW NW NE, Sec. 23-23-4W,  
Reno County, Kansas

L. A. Kefauver  
B