

15-155-025580000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

RENO County. Sec. 23 Twp. 23S Rge. 4 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines C SE NE 1/4
Lease Owner OLSON OIL COMPANY - Shell Oil Co., Inc.
Lease Name F. Duckworth Well No. 1
Office Address Drawer 588, Tulsa, Oklahoma
Character of Well (Completed as Oil, Gas or Dry Hole) Oil & Gas
Date, well completed 7 - 8 - 1932
Application for plugging filed 9 - 21 - 1939
Application for plugging approved 9 - 22 - 1939
Plugging Commenced 10 - 24 - 1939
Plugging Completed 10 - 28 - 1939
Reason for abandonment of well or producing formation Well went to water.
If a producing well is abandoned, date of last production 4 - 11 - 1939
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Chat Depth to top 3264 Bottom 3377 Total Depth of Well 3377 Feet.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Chat	Gas	3312	3346	15 1/2"	256	None
"	Oil & Gas	3346	3377	12 1/2"	483	323
				8 5/8"	3294	2664

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy mud from bottom 3377 to 3314. Dumped 15 sacks of cement with dump bailer, filled hole to 3260. Filled hole with mud from 3260 to 260, set wood plug and dumped 17 sacks cement at 260, filled to 246. Filled surface pipe with heavy mud from 246 to 6 ft. of base of cellar, put in 8 sacks of cement for top surface cap.

11-7-39

INDEXING
FILE NO. 23-23-46
BOOK PAGE 96 LINE 31



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to S. A. Keefover
Address Box 408, Burrton, Kansas

STATE OF KANSAS, COUNTY OF RENO, ss.
S. A. Keefover (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Keefover

(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of November, 1939

My commission expires 4/20/42

Notary Public. G. I. Bryan


15-155-62558-0000

OLSON OIL COMPANY
F. Duckworth # 1
C SE NE 23-23S-4W
RENO COUNTY, KANSAS

COMMENCED 5-30-32
COMPLETED 7-8-32
ELEVATION 1468'

0			
150	Sand	2568	Lime
235	Clay	81	Shale & shells
261	Sh & lime shells	93	Shale & lime
	--Set 15 1/2" W/200 sx.	2618	Lime
275	Clay	30	Broken lime
301	Lime	43	Shale
330	Lime & shale	60	Broken lime
434	Shale	2702	Sh & lime shells
437	Cavity	2718	Lime
442	Lime	47	Shale & lime
448	Cavity	63	Lime
498	Salt & lime shells	70	Broken lime
529	Sh & Lime shells	98	Shale
534	Sandy shale	2893	Lime
555	Broken lime	2905	Lime
800	Shale	10	Sand
815	Broken lime	19	Shale & lime
910	Shale & shells	28	Lime
918	Red rock	31	Lime, ool.
985	Sh & lime shells	75	Lime
999	Broken lime	3170	Lime & shale
1008	Lime	81	Broken lime
28	Broken lim	3264	Vqr. shale
60	Shale & lime shells	87	Chat
82	Shale	3310	"
91	Red rock	11	Lime
1656	Shale	12	Chat, set 8 1/2" W/250 sx.
1710	Sh & lime shells		R.U.S.T.
17	Red rock	3346	Chat, show of oil & gas
70	Shale	50	" " " " "
1965	Sh & lime shells	55	" " " " "
2003	Broken lime	77	" , TOTAL DEPTH
2173	Shale & lime shells		
2220	Shale		
2374	Sh & lime shells		
2389	Lime		
2559	Sh & lime shells		

PLUGGING	
FILE SEC	<u>23-T-23-R-4</u>
BOOK PAGE	<u>76-LINE 31</u>



Subscribed and sworn to before me
this 21st day of September 1939

I hereby certify that the above
is a true and correct copy of the log
of the F. Duckworth # 1, C SE NE/4,
Section 23-23S-4W, Reno County, Kansas

L. J. Bryan
Notary Public

S. A. Keefow

My commission expires April 20, 1942