


15-55-02549-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Reno County, Sec. 23 Twp. 23s Rge. 4 W (E) (W)
Location as "NE/CNW/WSW" or footage from lines SW-SE-NE
Lease Owner K & P Oil Company
Lease Name Vansickle Well No. 2
Office Address P.O. Box 559 Tulsa, Oklahoma 74101
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed 8-10 1973
Application for plugging approved 8-13 1973
Plugging commenced 8-17 1973
Plugging completed 8-21 1973
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3621' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		1000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3621' to 3590'. Dumped 6 sx of cement. Mudded hole to 255'. Made 15' of rock bridge. Dumped 9 Yrds of Ready-Mix cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of August, 1973

My commission expires January 5, 1974

[Signature]
Notary Public.

VanSickle Logs

S-31-3 U

KANSAS WELL LOG

15-155-02549-0000

MARATHON OIL COMPANY
S. E. VanSickle No. 2
Total Depth: 3621, P/B 3620
Comm: 12-20-34. Comp: 1-18-35.
Shot or treated: 1000 gal acid.

SW Cor SE 1/4
Sec. 23-23-4W,
Reno County, Kansas.
Pool - Burrton.

Casing Record:
15 1/2" 255
6 5/8" 3601

Production: 1312 Bbls. 24 hours.
Pumping potential.

Figures indicate Bottom of Formations.

Sand	90
shale and shells	165
shale and sand	180
shale shells	200
sand shells	230
shale	255
shale shells	590
shale lime	642
shale shells	730
shale	780
lime shale	895
shale lime shells	988
lime	1005
shale shells	1088
lime shale	1190
shale	1293
lime	1312
shale shells	1548
shale	1680
shale lime	1760
shale shells	1850
lime	1880
lime shale	1897
shale	1951
shale lime	1995
lime	2095
shale	2105
shale lime	2155
shale	2264
sand	2350
??	2370
shale	2550
lime	2940
shale and shells	2975
shale	3028
shale and shells	3088
shale	3249
lime	3271
ohat	3405
lime	3493
shale	3600 Top Hunton Lime
3587 equals 3592 SIM.	
3595 equals 3599 SIM.	
lime	3621 T.D.
Plugged back to 3620.	

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1973
CONSERVATION DIVISION
Wichita, Kansas

3600
~~1475~~

2130 -

3600
~~1475~~

2125