

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

15-155-20,187-000 WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # Spud 12/22/71 (Identifier number of this well); This must be listed for wells drilled since 1967; If no API# was issued, indicate spud or completion date. *6/95*

WELL OPERATOR Producers Oil Company KCC LICENSE # 5235  
(owner/company name) (operator's)

ADDRESS 427 So. Boston, STE 711 CITY Tulsa,

STATE Oklahoma ZIP CODE 74103 CONTACT PHONE # (918) 582-1188

LEASE Vansickle WELL# 6 SEC. 23 T. 23S R. 4W (East/West)

SW - NW - NW - SPOT LOCATION/QQQQ COUNTY Reno

1280 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE            SET AT            CEMENTED WITH            SACKS

SURFACE CASING SIZE 10 3/4 SET AT 241 CEMENTED WITH 260 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3610 CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 0/H 3610-15, Perfs 3323-80, CIBP 3310,

ELEVATION 1475 T.D. 3615 FBTD            ANHYDRITE DEPTH Perfs 3284-3290  
(G.L. K.A.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 3270 & cap w/2 sx. cem., perforate 5 1/2

@ 600' and spot 35 sx. 60/40 4% Poz mix plug, Perf. 5 1/2 @ 375' & circ. cement to

surface, cut off casing, weld on ID marker.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? NA

If not explain why?           

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Matt Riley PHONE# (405) 863-2784 (office)

ADDRESS Rt. 1 Box 45 City/State Covington, OK 73730

PLUGGING CONTRACTOR Sunflower Well Service KCC LICENSE # 30280 *12/94*

ADDRESS 408 N. 4th, P.O. Box 341, Canton, KS 67428 PHONE # 316 628-4723 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (if known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2/6/95 AUTHORIZED BY            KANSAS CORPORATION COMMISSION  (signature)

FEB 13 1995

CONSERVATION DIVISION  
WICHITA, KS



## Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director Brian Moline, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 13, 1995

Producers Oil Company  
427 S Boston Ste 711  
Tulsa OK 74103

Vansickle #6  
API 15-155-20, 187-00-01  
1280 FNL 330 FWL  
Sec. 23-23S-04W  
Reno County

Dear Matt Riley,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams  
Production Supervisor

District: #2  
130 S. Market Room 2078  
Wichita KS 67202-3208  
(316) 337-6231