

15-095-01526-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Kingman

County. Sec. 15 Twp. 27S Rge. (E) 10W (W)

Location as "NE/CNW/SW" or footage from lines Center of SE/4, SW/4, NE/4

Lease Owner Amerada Petroleum Corporation

Lease Name Helena Stroot

Well No. 2

Office Address Box 197 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.

Date well completed May 19, 1956

Application for plugging filed May 19, 1956

Application for plugging approved May 19, 1956

Plugging commenced May 19, 1956

Plugging completed May 19, 1956

Reason for abandonment of well or producing formation Dry Hole.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4341' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud to 300' from top, set 1/4 sack hulls & bridge plug at 300', spotted 20 sacks cement thru drill pipe, filled hole with heavy mud to 35' from top, set 1/4 sack hulls & bridge plug at 35', mixed & dumped in 10 sacks cement filling surface casing to top.

RECEIVED
STATE CORPORATION COMMISSION

MAY 22 1956

05-22-56

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Co.

Address 1612 First Nat'l. Bldg. - Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.

R. A. Drake

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. A. Drake

Box 197 - Great Bend, Kansas.

(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of May, 1956

Charles E. Stenison

Notary Public.

My commission expires June 24, 1959

24-2675-S 2-52-20M

PLUGGING
FILE SEC 15 T. 27 R. 10W
BOOK PAGE 63 LINE 23

WELL LOG

15-095-01526-0000

Helena Stroot #2
SE/4, SW/4, NE/4
Sec. 15-27S-10W, Kingman County, Kansas.

0'	-	185'	Sand
185'	-	343'	Red Bed
343'	-	615'	Red Bed & Shale
615'	-	1160'	Shale
1160'	-	1420'	Shale & Shells
1420'	-	1460'	Lime
1460'	-	1548'	Shale & Shells
1548'	-	1720'	Shale & Lime
1720'	-	1815'	Lime
1815'	-	1950'	Lime & Shale
1950'	-	2270'	Shale & Lime
2270'	-	2450'	Shale
2450'	-	2600'	Shale & Lime
2600'	-	3055'	Shale
3055'	-	3155'	Lime & Shale
3155'	-	3284'	Shale & Lime
3284'	-	3405'	Lime & Shale
3405'	-	3505'	Shale & Lime
3505'	-	3555'	Lime & Shale
3555'	-	4018'	Lime
4018'	-	4072'	Cherty Lime
4072'	-	4112'	Shale
4112'	-	4180'	Lime & Shale
4180'	-	4288'	Shale & Lime
4288'	-	4295'	Lime
4295'	-	4310'	Lime & Chert
4310'	-	4341'	Lime.
T.D.	-	4341'	

RECEIVED
STATE CORPORATION COMMISSION

MAY 22 1966

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 15 T 27 R 10W

BOOK PAGE 63 LINE 23