


15-09501607-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail of Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

R
WELL PLUGGING RECORD

Kingman County. Sec. 15 Twp. 27 Rge. (E) 10 (W)
Location as "NE/CNW/SW" or footage from lines C E/2 NE SE
Lease Owner Tennessee Gas Transmission Company
Lease Name Albert McCartney Well No. 3
Office Address P. O. Box 163 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-26 19 54
Application for plugging filed 12-18 19 59
Application for plugging approved 12-18 19 59
Plugging commenced 1-4 19 60
Plugging completed 1-8 19 60
Reason for abandonment of well or producing formation Well reached economic limit
If a producing well is abandoned, date of last production October 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Viola Depth to top 4290' Bottom 4294' Total Depth of Well 4292' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262'	None
				5-1/2"	4367'	3255'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bailed hole to 250', set Rock Bridge from 250' to 240', Placed 20 sacks cement from 240' to 180', Mudded from 180' to 40', Set Rock Bridge from 40' to 30', Ran 10 sacks cement from 30' to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Glen E. Armour (employee of owner) ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour
P. O. Box 163 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of January, 19 60

My commission expires October 13, 1962 John Lemov Notary Public.



JAN 14 1960

CONSERVATION DIVISION
WICHITA, KANSAS

15-095-010070000

Bennett & Roberts Oil Oper.
McCartney #3

CE/2 NE SE Sec. 13-27-10
Kingman County, Kansas

R.T.D. 4292

Mississippi
Viola

Tops:
4025--2264
4290-2529

Comm: 7/8/54
Comp: 7/26/54

8 5/8" Set @ 262' w/273 sz cnt.
3 1/2" Set @ 4290' w/100 sz cnt.

Formation:	Depth:
Sand & Red Bed	249'
Red Bed	262
Shale & Red Bed	1467
Lime & Shale	1650
Broken Lime	1736
Shale, Sand Stks.	1783
Lime & Shale	1920
Shale	2336
Shale & Sand Stks.	2570
Lime & Shale	3033
Shale	3210
Shale & Lime	3340
Lime	3405
Lime & Shale	3485
Lime	4018
Lime & Shale	4037
Chat	4070
Lime & Chat	4091
Lime	4292

STATE OF KANSAS
CONSERVATION COMMISSION

DEC 18 1959

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

Barbara A. Just

Subscribed and sworn to before me this 29th day of July, 1954.

Clara L. Linn
Notary Public

My Commission Expires 6/17/58