


15-095-01671-0006

Form CP-4

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 212 No. Market
 Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 15 Twp. 27 Rge. 10 (E) W (W)
 Location as "NE/CNW/SW" or footage from lines SE SE SE
 Lease Owner SPECTER PIPE & SUPPLY, COMPANY, INC.
 Lease Name McCartney Well No. 1
 Office Address Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed 9-1-52 19
 Application for plugging filed Jan. 5, 1970 19
 Application for plugging approved Jan. 6, 1970 19
 Plugging commenced January, 24, 1970 19
 Plugging completed February, 7, 1970 19
 Reason for abandonment of well or producing formation failure to produce profitably
 If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas
 Producing formation Mississippi Depth to top 4029 Bottom 1332 ft. Total Depth of Well 4342 ft. Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4" OD	203 ft.	none
				7" OD	4355 ft.	3010 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 4000- Feet, dumped, 5- sacks cement.
 Mudded hole up to 200- feet, Set a Rock Bridge.
 Dumped 35- sacks Cement, Mudded hole up to 40 -feet.
 Set a Rock Bridge, 20- sacks on top.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 12 1970
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor LYNCH CASING PULLING, COMPANY NO. 457
 Address R. Rt. 4 GREAT BEND, KANSAS. 67530

STATE OF Kansas COUNTY OF Russell, ss.
 Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of February, 19 70

 Elsie Coady Notary Public.

ELSIE COADY
 NOTARY PUBLIC
 My commission expires December 1, 1972
 WICHITA COUNTY, KANSAS

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-095-01671-0001

Company: B. & R. DRILLING CO.
Farm: McCartney No. 1

SEC. 15 T. 27 R. 10W
SE SE SE

Total Depth. 4342
Comm. 8-16-52 Comp. 9-4-52
Shot or Treated.
Contractor.
Issued. 2-21-53

County Kingman
KANSAS



CASING:
10 3/4 set at 203 w/ 225 sx cement
7 in. set at 4335 w/ 50 sx cement

Elevation. 1753

Production. 161 BQ, 18 BW

Figures indicate Bottom of Formations.

sand & shells	100
sand	182
red rock, shale & shells	330
red bed	490
sand & shale	520
shale	730
anhydrite	750
shale & shells	1100
shale & salt	1330
lime & shale	1470
lime, shale & shells	1630
lime & shale	1875
lime	1960
lime & shale	1975
lime	2020
shale & lime	2845
lime	2920
shale	2990
lime	3030
lime & shale	3105
lime	3170
lime & shale	3410
lime	3457
lime & shale	3560
lime	3697
lime & shale	3732
lime	3795
lime & shale	3840
lime	3886
lime & shale	3930
lime	4018
lime & shale	4030
lime & chert	4097
shale	4100
shale & lime	4264
shale	4333
lime	4342
Total Depth	

SCOUT TOPS:	
Anhydrite	730
Brown lime	3510
Lansing	3519
Mississippi	4029
Viola	4333

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1960
CONSERVATION DIVISION
Wichita, Kansas