

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-2025000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Maxdon

WELL NUMBER # 1

SPOT LOCATION C SE SW

SEC. 15 TWP. 27S RGE. 10W (E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 4-2-86

Plugging Completed 4-9-86

LEASE OPERATOR Patton Oil Company

ADDRESS 672 W. 4th St. Hoisington, Kansas 67544

PHONE # (316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 2390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	227'	none
				4-1/2"	2385'	1613'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 2298' and 4 sacks cement. Shot pipe @1935', 1815', 1725', 1613' and pulled a total of 41 joints of 4-1/2" casing (1613'). Plugged surface with 2 hulls, 12 gel, 30 60/40 pos, 6% gel, 3% cc., 3 gel 1 hull, 8-5/8" plug and 70 60/40 pos, 6% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss. RECEIVED
STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

APR 13 1986
CONSERVATION DIVISION
Wichita, Kansas


(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 11th day of April, 1986

Jane Hoover
Notary Public

My Commission expires: _____



15-095-20825000

BIG SPRINGS DRILLING, INC.

P.O. BOX 8287
MUNGER STATION
WICHITA, KANSAS 67208

SUITE 29 • 400 NORTH WOODLAWN • (316) 681-1732

March 28, 1979

DRILLERS LOG

Re: Maxdon No. 1
C SE SW
Sec. 15-Twp 27s- Rq 10W
Kingman County, Kansas


OPERATOR: Patton Oil Company
CONTRACTOR: Big Springs Drilling, Inc.
COMMENCED: 3-18-79
COMPLETED: 3-22-79

Surface Pipe: 227' of 8 5/8" w/175 sx Common 2% gel 3% ccl


0	227	Sand
227	600	Sand, Shale and Red beds
600	1325	Shale
1325	1600	Lime and Shale
1600	1670	Shale
1670	2370	Lime and Shale
2370	2390	Lime
2390		RTD

We certify that the above and foregoing is a true and correct copy of the log on the # 1 Maxdon located in Kingman County, Kansas.

BIG SPRINGS DRILLING, INC.


Paul A. Seymour, Jr.

Subscribed and sworn to before me this 28th day of March, 1979.


Ruth M. Bassett Notary Public

My Commission Expires:

May 30, 1979

RECORDED
STATE CORPORATION COMMISSION

MAR 27 1985

CONSERVATION DIVISION
Wichita, Kansas