

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15095-20,712-0000

LEASE NAME Bradshaw

WELL NUMBER 1-B

 Ft. from S Section Line

 Ft. from E Section Line
 C NE NE SE

SEC. 12 TWP. 27S RGE. 10W (E) or (W)

COUNTY Kingman

Date Well Completed

Plugging Commenced 7-24-87

Plugging Completed 8-6-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Patton Oil Company

ADDRESS 672 W. 4th
Hoisington, Kansas 67544

PHONE# (316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well Pil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #2 Wichita, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 2225'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	261'	none
				4-1/2"	1672'	313'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped bottom with 35 sacks cement to 1230'. Shot pipe @345', laid down 8 joints of 4-1/2" casing. Plugged surface with 2 hulls, 12 gal, 110 cement, 60/40 pos, 4% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) Box 347
Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 87

James Hoover
 Notary Public

My Commission Expires:



STATE CORPORATION COMMISSION

RECEIVED
 AUG 17 1987 Form CP-4
 Revised 07-86
 08-17-87
 CONSERVATION DIVISION
 Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Patton Oil Co.

SEC. 12 T. 27S R. 10W

FARM Bradshaw

NO. 1-"B"

LOC. C-NE NE SE

COUNTY Kingman

ROTARY TOTAL DEPTH 2,225'
COMM. May 3, 1978
CONTRACTOR H-30, Inc.
ISSUED May 15, 1978

COMP. May 8, 1978

CASING

10 3/4"

8 5/8" Set at 261' cemented w/210 sxs cement

ELEVATION 1,754 K.B.

5 1/2"

4 1/2" Set at 1,672' cemented w/200 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	160'
Red Bed	602'
Red Bed and Shale	910'
Shale	1,360'
Anhydrite	1,369'
Lime and Shale	2,225'
Rotary Total Depth	2,225'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick }

SS:

Suscribed and Sworn to before me a Notary Public in and for said county and state this 15th day of May, 1978.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1987

CONSERVATION DIVISION
Wichita, Kansas