

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-095-217510000
LEASE NAME Kelly
WELL NUMBER No. 1

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

990 Ft. from South Line of Section
2050 Ft. from East Line of Section

LEASE OPERATOR R & B Oil & Gas SPOT LOCATION 70' W of C N/2 Sw Se
ADDRESS 904 N. Logan, PO Box 195 Section 12 Township 27s Range 10w
CITY, STATE, ZIP Attica, Kansas 67009-0195 County Kingman
PHONE # 316-254-7972 Date Well Completed April 19, 1999
Character of Well Dry and Abandoned Date Plugging Commenced April 19, 1999
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed April 19, 1999

The plugging proposal was approved on April 13, 1999 at 10:45 am (date)
by Mike Willson (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 1675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	150	and		
Redbeds	Shale/Siltstone	150	235	8-5/8"	225.56	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugging began at 2:00 pm and ended at 3:30 pm on 04-19-99 using 60/40 Poz, 4% Gel:

Heavy mud from 1675' to 1425' then 35 sacks, heavy mud to 950' then 35 sacks,
heavy mud to 280' then 35 sacks, heavy mud to 60' then 25 sacks.

Plugged by Allied Cementing, Ticket # 6922.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 29th day of April, 1999

RECEIVED
STATE OF KANSAS



04-30-99

[Signature]
(Notary Public)

WICHITA, KANSAS

My Commission Expires: _____

15-095-21751-0000

Sterling Drilling Company, Rig #8

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Kelly No. 1

LOCATION: 70' W of C N/2 Sw Se Section 12 T 27s R 10w
API: 15-095-217510000 Kingman County, Kansas

OWNER: R & B Oil & Gas
CONTRACTOR: Sterling Drilling Company, Rig #8

COMMENCED: 12-Apr-99
COMPLETED: 19-Apr-99

TOTAL DEPTH: **DRILLER** 1675 FEET
LOGGER Not Logged FEET

Ground Elevation: 1775
KB Elevation: 1779

LOG

0 - 150 FEET Top Soil and Fresh Water Sands
150 - 985 FEET Redbeds
985 - 1575 FEET Hutchinson Salt and Anhydrites
1575 - 1675 FEET Dolomite/Limestone

CASING RECORDS

Surface/Production Casing Data:

Spud @ 8:00 am on 04-12-99. Drilled 12 1/4" hole to 235'. Ran 6 joints of 28# 8-5/8" surface casing 225.56' set at 231' KB. Cemented with 200 sacks 60/40 Poz, 2% Gel, 3% CC.

Plug down at 3:45pm on 04-12-99 by Allied. Good returns. Ticket # 2562.

Plugging began at 2:00 pm and ended at 3:30 pm on 04-19-99 using 60/40 Poz, 4% Gel:
Heavy mud from 1675' to 1425' then 35 sacks, heavy mud to 950' then 35 sacks,
heavy mud to 280' then 35 sacks, heavy mud to 60' then 25 sacks.
Plugged by Allied Cementing, Ticket # 6922.
Received plugging orders from Mike Willson at 10:45 am on 04-13-99.

DEVIATION SURVEYS

1/2 degree(s) at 235 feet
1 degree(s) at 1605 feet

RECEIVED
STATE COMMISSION

APR 30 1999

CONSERVATION DIVISION
Wichita, Kansas