


15-049-19222-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-1

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

E 1k County, Sec. 34, Twp. 29, Rge. 10E (E) (W)
Location as "NE/CNW/SW" or footage from lines: Near C of SE 1/4 NW 1/4
Lease Owner: Carl Criger
Lease Name: Dunkleburger Well No. 4-input
Office Address: Howard, Kansas
Character of Well (completed as Oil, Gas or Dry Hole): input
Date well completed: June 1954
Application for plugging filed: Sept. 26, 1974
Application for plugging approved: Sept. 25, 1974
Plugging commenced: Sept. 27, 1974
Reason for abandonment of well or producing formation: depleted
If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Bert Wilcox
Producing formation: Depth to top: Bottom: Total Depth of Well 1320 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		976'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bridged hole at 971', rocks and dumped 3 sacks cement.
Bridged hole at 200', rocks and 12 sacks cement.
Bridged hole at 40 ft. rocks and 8 sacks cement to top.


RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Lewis C. Long
Address: Hamilton, Kansas

STATE OF Kansas, COUNTY OF Greenwood, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. C. Long
Hamilton, Kansas (Address)



SUBSCRIBED AND SWORN TO before me this 26th day of August, 1974

My commission expires 14 February 1977
Mary Bonczkowski, Notary Public.

TOM HENDRICKSON, PRESIDENT

J. E. BRINEGAR, SECRETARY

CARL MORROW, TREASURER

#4

Location: Near the center of the SE 1/4 NW 1/4 of Sec. 36
Township 29 South, Range 10 East.

ELK DRILLING CO., INC.

HOWARD, KANSAS

Morrow & Co., Operators

Well No. 4- Dunkleburg- Input-
May 1954.

Completed 6-7-1954

soil	21
gravel	24
shale	42
lime	55
shale	70
lime	78
shale	88
lime	97
shale	102
lime	113
shale	118
lime	120
shale	127
red rock	140
lime	147
shale	156
sandy shale	170
shale, blue	183
lime	190
shale	198
lime	210
shale	320
sand 2-BW	343
shale	395
lime, hard	403
shale, black	405
lime	418
red rock	460
shale	475
lime	488
shale	496
red rock	501
shale	512
red rock	517
shale	530
lime	532
shale	573
sand 2-BW	602
shale	678
lime	685
shale	700
sand	712
red rock	720
shale	736
lime	758
shale	770
lime	773
sand	780

shale	800
lime	808
shale	815
Big lime	938 HW 840-860
shale	1100-steel line
gas cap	1110
shale	1117
lime	1121
shale	1140
lime	1144
shale	1151
lime	1161
shale	1170
lime shells	1185 reduced 8 to 7"
lime	1286 1193
shale, black	1288-casing spot 1288
cap rock, dark	
lime	1290- S.L. 1289
lime	1295
sand, oil	1297
sand	1318
shale	1320

shot from 1295 to 1318' w₁th
52 qts.
cemented with 24 sacks

Casing record.

Casing record-

12"	40' 3" pulled
10"	348' 6" "
8"	730' 1/2-sack aquagel
5"	1288' 6" "

3 joint 6 in cemented with 5
S_{1/2} cent for surface

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1974

CONSERVATION DIVISION
Wichita, Kansas