


15-155-20258-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. BOX 17027
Wichita, Kansas 67217
NORTH

Reno County, Sec 22 Twp. 23S Rge. 4W (E) (W)
Location as "NE/CNW/SW" or footage from lines 220'S of C NW NE SE
Lease Owner TGT Petroleum Corporation
Lease Name Hilda #2 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 12/14/74 19____
Plugging completed 12/23/74 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation... Depth to top... Bottom... Total Depth of Well 3399 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	182	none
				8-5/8	614	498'
				5 1/2"	3399	3137'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded bottom off and dumped 5 sacks cement. Shot pipe at 3200', 3100', pulled 96 joints. Set bridge 600 to 614' with 10 sacks cement. Shot 8 5/8" at 480, 420', pulled 10 joints. Made bridge at 200' and dumped 35 sacks cement. Set bridge 40 to 30' and dumped 15 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor JIM'S PIPE PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
JAMES R. GILLESPIE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Gillespie
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1974

MARGARET
NOTARY PUBLIC
County, Kansas
Commission Expires 2. 15. 1975


Margaret Melcher
Notary Public.

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1975

CONSERVATION DIVISION
Wichita, Kansas



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

September 27, 1974

15-155-20258-0000

COMPANY: TGT PETROLEUM CORPORATION
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: HILDA #2
 LOCATION: 220' S. of C NW NE SE, Section 22-23S-4W, Reno County, Kansas
 COMMENCED: September 19, 1974
 COMPLETED: September 27, 1974
 ELEVATION:

0	to	50	Clay & Sand
50	to	140	Blue Shale
140	to	182	Shale
182	to	580	Shale & Lime
580	to	796	Lime
796	to	865	Lime & Shale
865	to	1085	Lime
1085	to	1365	Lime & Shale
1365	to	1960	Shale & Lime
1960	to	2395	Lime
2395	to	2625	Lime & Shale
2625	to	3250	Lime
3250	to	3278	Shale
3278	to	3400	Mississippi
		3400	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 11 1974
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 15 1/4 inch hole to 182' and run 184' of 10 3/4 inch O. D. casing, cemented with 175 sacks of 3% C. C., plug down at 12:00 Noon, September 20, 1974. Reamed 9 7/8 inch hole to 620' and run 616' of 8 5/8 inch O. D. casing, cemented with 100 sacks of 3% C. C. at 614', plug down at 1:25 P. M., September 21, 1974. Drilled 7 7/8 inch hole to 3400'. Run 3415' of 5 1/2 inch O. D. casing, cemented with 100 sacks of cement (60/40 posmix) 1 foot off bottom at 3399', plug down at 8:30 A. M., September 27, 1974.

TOPS: MISSISSIPPIAN - 3278'

Measurements taken from K. E.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Hilda #2, located on the 220' S. of C. NW NE SE, Section 22-23S-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

Charles D. Johnson, Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 27th day of September, 1974.

Johnnie L. Schmidt - Notary Public

