

15-155-20197-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 22 Twp. 23S Rge. 4 W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NE NW NE
Lease Owner T. G. T. Petroleum Corporation
Lease Name Miller "A" Well No. 6
Office Address 209 East William St. Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed March 1974
Application for plugging approved March 1974
Plugging commenced April 1 1974
Plugging completed April 4 1974
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3362' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,845'
				8"		413'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3362' to 3350'. Dumped 5 sx of cement. Mudded hole 450'. Made 5' of rock bridge. Dumped 4 sx of cement. Mudded hole to 215'. Made 15' of rock bridge. Dumped 4 Yrds. of Ready-Mix cement, filling to the bottom of the collar.

RECEIVED
STATE CORPORATION COMMISSION
APR 8 - 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this April 19 74

My commission expires December 31, 1977

Judy Lamb
Notary Public.

15-155-20197-0000

ROTARY DRILLERS' LOG

OPERATOR: Rosen Oil Corporation DRILLING COMMENCED: March 24, 1972
200 Sutton Place
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: March 30, 1972
505 Union Center
Wichita, Kansas 67202

CASING RECORD: 10 Jts. 216' 10-3/4" cemented with 215 sacks.
15 Jts. 608' 8-5/8" cemented with 100 sacks.
158 Jts. 3433' 5-1/2" cemented with 75 sacks.

LOCATION: Miller "A" No. 6
NE NW NE
Section 22-23S-4W
Reno County, Kansas

- 0 - 40 Sod & sand
- 40 - 535 Shale & shells
- 535 - 615 Dry drilled
- 615 - 728 Lime & shale
- 728 - 770 Red rock
- 770 - 1085 Shale & lime streaks
- 1085 - 1485 Lime & shale
- 1485 - 1930 Shale & shells
- 1930 - 2203 Shale & lime
- 2203 - 2330 Lime
- 2330 - 2580 Shale & lime
- 2580 - 2735 Lime & shale
- 2735 - 3090 Lime
- 3090 - 3220 Lime & shale
- 3220 - 3430 Lime
- 3430 Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1974
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Phil Graves

STATE OF KANSAS)
) ss.
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 3rd day of April, 1972.

My commission expires:
May 9, 1975

Betty Brandt
Betty Brandt Notary Public

Copy to Corporation Commission #6 Miller "A" well file
Copy to Milling Bureau