

JAN 29 1971

CONSERVATION DIVISION  
Wichita, Kansas


Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD 15-155-26093-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Flat

Reno County, Sec. 22 Twp. 23 Rge. 4 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner John C Graves et al  
Lease Name Dillingham Well No. #1  
Office Address 505 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 1-15-71 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 1-22-71 19\_\_\_\_  
Plugging completed 1-27-71 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3412' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3407'	2770.52'
				10 3/4"	230'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 3390'. Mixed and ran 5 sacks cement thru dump bailer.  
Bailed hole down to 230', set 10' rock bridge. Mixed and dumped 35 sacks cement  
Mudded hole to 40', set 10' rock bridge. Mixed and dumped 15 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of January, 19 71

My commission expires October 1972  
Sidney D. Miller  
Notary Public.

**ROTIARY DRILLERS' LOG**

15-155-20093-0000

**OPERATOR:** <sup>Graves</sup> ~~Rosen Oil Company~~  
603 Sutton Place  
Wichita, Kansas

**DRILLING COMMENCED:** 1-15-69  
SE SE SW  
Sec. 22-23S-4W  
Reno County

**CONTRACTOR:** Graves Drilling Co., Inc.  
502 Union Center  
Wichita, Kansas

**DRILLING COMPLETED:** 1-21-69

**CASING RECORD:** 230' of 10 3/4" surface casing, 275 sacks cement; 3 1/2" pipe set at 3,407'; 135 sacks cement.

**LOCATION:** Dillingham #1  
SE-SE-SW  
22-23S-4W,  
Reno County, Ks.

-----

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 3 1971  
CONSERVATION DIVISION  
Wichita, Kansas

0	-	13	Soil
18	-	210	Sand
210	-	242	Red rock
242	-	595	Shale
595	-	1255	Shale and shells
1255	-	1628	Line with shale streaks
1628	-	2006	Shale
2006	-	2415	Line
2415	-	2682	Shale and shells
2682	-	3070	Line
3070	-	3293	Shale and shells
3293	-	3410	Line and chert
3410			Total Depth

I hereby certify the foregoing statements to be true and correct, to the best of my knowledge.

GRAVES DRILLING CO., INC.

By \_\_\_\_\_  
President

STATE OF KANSAS )  
                          ) ss  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public this 27th day of January, 1969.  
My commission expires: July 28, 1970

\_\_\_\_\_  
Mary Ann Scott, Notary Public

*[Handwritten signature/initials]*